

AD-A099 059


CORPS OF ENGINEERS BALTIMORE MD BALTIMORE DISTRICT
NATIONAL DAM INSPECTION PROGRAM. LAKE GUINN DAM (NDI ID NUMBER --ETC(U)
FEB 81

F/G 13/13

UNCLASSIFIED

NL

1 OF 2
AD-A
099059



AD A099059

DELAWARE RIVER BASIN
TRIBUTARY TO MIDDLE CREEK, WAYNE COUNTY

PENNSYLVANIA


LAKE QUINN DAM

NDI ID NO. PA-00145

DER ID NO. 64-43

MR. DAVID BEYNON, SR.

PHASE I INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



DTIC
ELECTE
MAY 18 1981
A

This report has been approved
for publication and sale; its
distribution is unlimited.

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

81 5 18 005

DELAWARE RIVER BASIN
TRIBUTARY OF MIDDLE CREEK, WAYNE COUNTY
PENNSYLVANIA

(t) National Dam Inspection Program.

LAKE QUINN DAM

(NDI ID ^{PA-00145}
DER ID NUM ⁶⁴⁻⁴³)

~~MR. DAVID BEYRON, SR.~~

Delaware River Basin, Tributary
of Middle Creek Wayne County,
Pennsylvania.

PHASE I INSPECTION REPORT.

NATIONAL DAM INSPECTION PROGRAM

(12) 100

Prepared by

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers
Baltimore, Maryland 21203

(11) February 1981

Original contains color
All other reproductions
shall be in black and

409111

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the spillway design flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The spillway design flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

CONTENTS

<u>Description</u>	<u>Page</u>
Brief Assessment of General Condition and Recommended Action.....	iii
SECTION 1 - Project Information.....	1
SECTION 2 - Engineering Data.....	7
SECTION 3 - Visual Inspection.....	9
SECTION 4 - Operational Procedures.....	13
SECTION 5 - Hydrology and Hydraulics.....	15
SECTION 6 - Structural Stability.....	20
SECTION 7 - Assessment, Recommendations, and Proposed Remedial Measures.....	23

APPENDICES

<u>Appendix</u>	<u>Title</u>
A	Checklist - Visual Inspection.
B	Checklist - Engineering Data.
C	Photographs.
D	Hydrology and Hydraulics.
E	Plates.
F	Geology.

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

BRIEF ASSESSMENT OF GENERAL CONDITION

AND

RECOMMENDED ACTION

Name of Dam:

Lake Quinn Dam
NDI ID No. PA-00145
DER ID No. 64-43

Size:

Small (12.2 Feet high; 305 acre-feet)

Hazard Classification:

High

Owner:

Mr. David Beynon, Sr.
Rd 2, Lake Quinn
Box 125
Waymart, PA 18472

State Located:

Pennsylvania

County Located:

Wayne

Stream:

Tributary of Middle Creek

Date of Inspection:

4 November 1980

-X The visual inspection and review of available design and construction information indicate that Lake Quinn Dam is in fair condition. Deficiencies noted during the inspection included the lack of functional drawdown facilities and minor seepage through the masonry near the right abutment.

Based on the size and hazard classification of the dam, the recommended Spillway Design Flood (SDF) varies between $\frac{1}{2}$ the Probable Maximum Flood (PMF) and the PMF. The $\frac{1}{2}$ PMF has been selected as the SDF due to the size of the dam and reservoir, and the downstream conditions. The hydrologic and hydraulic computations indicate that the combination of reservoir storage and spillway discharge capacity will pass only 3 percent of the PMF without overtopping the dam. Overtopping the dam could cause failure, which would lead to a significant increase in downstream loss of life and property damage. Therefore, the spillway for Lake Quinn Dam is considered to be seriously inadequate, and the dam is judged to be unsafe, non-emergency.

It is recommended that the owner immediately:


- (1) Retain a qualified professional engineer to perform a detailed hydrologic and hydraulic study to further assess the discharge capacity of the spillway and develop remedial measures found necessary to provide adequate spillway capacity. This study should also include development of an adequate drawdown facility for the dam having positive upstream closure capability.
- (2) Seal the existing sluiceway, unless rehabilitation is undertaken.
- (3) Monitor, the seepage near the right abutment and take appropriate remedial action should the condition begin to worsen significantly.
- (4) Remove trees and brush from the abutments, and the cable and wire from the upstream face.
- (5) Develop formal surveillance and downstream emergency warning system for use during periods of heavy or prolonged precipitation.

LAKE QUINN DAM

- (6) Prepare an operation and maintenance manual or plan for use as a guide in the operation of the dam during normal and emergency conditions.
- (7) Develop a schedule of regular inspections by a qualified engineer.

Approved by:

DEPARTMENT OF THE ARMY
Baltimore District, Corps of Engineers


DATE: 9 APR 81
JAMES W. PECK
Colonel, Corps of Engineers
District Engineer

LAKE QUINN DAM



OVERVIEW

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

LAKE QUINN DAM

NDI ID NO. PA 00145

DER ID NO. 64-43

SECTION 1 - PROJECT INFORMATION

1.1 General

A. Authority

The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of non-Federal dams throughout the United States.

B. Purpose

The purpose of this inspection is to determine if the dam constitutes a hazard to human life and property.

1.2 DESCRIPTION OF PROJECT

A. Description of Dam and Appurtenances

Note: The U.S.G.S. Quadrangle Sheet (Waymart, Pa.) indicates a reservoir elevation of 1352, which is used in this report as existing spillway crest elevation.

Lake Quinn Dam is an earthfill and dry stone masonry structure with an overflow spillway section and concrete cap. The overall dam length is approximately 150 feet and the low point of the dam's crest is 12.2 feet above the downstream toe. The spillway is an uncontrolled broad-crested weir having a length of 66 feet. There are no functional outlet facilities for the dam. The present spillway crest is 1 foot below top of dam.

Available records indicate that the dam was lengthened and reinforced by placing random fill on the upstream face at the masonry dam, sometime after 1946. A sluiceway (currently inoperable) was also constructed in the old millrace at that time. All normal inflow is discharged through the uncontrolled spillway at the present time.

B. Location: South Canaan Township, Wayne County

U.S.G.S. Quadrangle - Waymart, Pa.

Latitude $41^{\circ} 30.5'$, Longitude $75^{\circ} 25.6'$

Ref. Appendix E, Plates I & II

C. Size Classification: Small: Height - 12.2 feet

Storage - 305 Acre-feet

D. Hazard Classification: High (Refer to Section 3.1.E)

E. Ownership: Mr. David Beynon, Sr.

RD2 Lake Quinn

Box 125

Waymart, PA 18472

F. Purpose: Recreation

G. Design and Construction History. No information on the original design and construction of the dam is known to exist. Sketches are available showing proposed work to be done in the late 1940's; however, it is not known specifically when this work was actually accomplished. Visual examination of the existing structure and available photographs indicate that, with some dimensional changes, the work proposed in 1946 was done sometime prior to 1965.

H. Normal Operating Procedure. The reservoir is normally maintained at the crest level of the uncontrolled spillway. Inflow occurring when the lake is at or above the spillway crest is discharged thru the uncontrolled spillway.

1.3 Pertinent Data:

A. Drainage Area (square miles)

From files:	4.7
Computed for this report:	9.7
Use:	9.7

B. Discharge at Damsite (cubic feet per second)

Maximum known flood	Unknown
Spillway at maximum pool (El. 1353.0)	200

C. Elevations (feet above mean sea level)

Note: Reservoir elevation of 1352.0 shown on
Waymart, Pa. U.S.G.S. quad is used as
spillway crest elevation.

Top of dam (low point)	1353.0
Top of dam (design)	Unknown
Spillway crest (current)	1352.0
Spillway crest (design)	Unknown
Streambed at toe	1340.8

D. Reservoir Length (miles)

Spillway crest (El. 1352.0)	1.6
Maximum pool (El. 1353.0)	1.7

E. Storage (acre-feet)

Spillway crest (El. 1352.0)	190
Maximum pool (El. 1353.0)	305

F. Reservoir Surface (acres)

Spillway crest (El. 1352.0)	104
Maximum pool (El. 1353.0)	125

G. Dam

Note: Refer to plates in Appendix B for
plan and section

Type: Dry stone masonry w/earthfill upstream;
concrete cap on crest.

Crest Length: 150 feet (incl. spillway)

Height: 12.2 feet (field measured; low pt.
to d/s toe)

Crest Width: 18.5' left of the spillway

7.4' between spillway and right abutment

Side Slopes:

Upstream: Vertical, upper 1.5' of left end
and flat below this depth
1V:8H at spillway

Downstream: Vertical

Zoning: Dry stone masonry w/earthfill upstream

Cutoff: None reported; placed on bedrock

Grouting: None reported.

H. Outlet Works: None

I. Spillway:

Type: Uncontrolled, rectangular concrete with broad crest

Length: 66 feet

Location: Middle of dam

Low Flow Notch: None

Approach Channel: Reservoir

Downstream Channel: Bedrock bottom

SECTION 2

ENGINEERING DATA

2.1 Design

The available data for Lake Quinn Dam consist of files provided by the Pennsylvania Department of Environmental Resources (PennDER). Information available includes state inspection reports, various related correspondence, and three rough sketches dated April 1946 showing proposed improvements to the dam. No other plans or design details are known to exist.

2.2 Construction

No information is available on the original construction of the dam. Records indicate that the repairs planned in 1946 were eventually accomplished, although the specific date is unknown. This work included strengthening the masonry section by placing random earthfill on the upstream side and extending the dam to its present length. A battered masonry downstream face was also to have been added, but was apparently never constructed. PennDER inspection reports indicate that a clay blanket was placed on the upstream face in the early 1970's to stop leakage thru the dam.

2.3 Operation

No formal records of operation or maintenance exist. The owner lives near the left abutment of the dam and checks the dam regularly to determine if maintenance is necessary. The owner stated that, to his knowledge, the greatest spillway flows occurred during the 1955 and 1972 storm events, with

each causing a flow depth of approximately 2.5 feet over the dam and spillway. The most recent PennDER inspection report (4 October 1972) indicated that the dam was in satisfactory condition at that time.

2.4 Evaluation

a. Availability

All available written information and data was contained in the permit files provided by PennDER.

b. Adequacy

The available data, including that collected during the recent detailed visual inspection, are considered to be adequate to make a reasonable assessment of the dam.

SECTION 3

VISUAL INSPECTION

3.1 Findings

A. General

The overall appearance of the dam is fair. The concrete cap on the dam and spillway is spalling and there are no facilities with which to draw down the lake. On the day of inspection, the pool was at its normal level with 0.1 feet of water flowing over the spillway (overflow section).

The visual inspection checklist and sketches of the general plan, profile, and section of the dam, as surveyed during the inspection, are presented in Appendix A. The survey datum is the reservoir elevation obtained from the U.S.G.S. Waymart, PA, quadrangle map. The owner, Mr. David Beynon Sr., was present during the inspection.

Photographs taken on the day of inspection are reproduced in Appendix C.

B. Stone Masonry and Embankment

Although there are some surface cracks and spalling of the 6"-10" thick concrete cap, no evidence of structural distress exists. The crest alignment, both horizontal and vertical, is good with no indications of movement. The downstream face of the dry-laid stone is in fair condition with

only a few stones missing. However, the old sluiceway has apparently been loosely filled with stone and timber and could be probed to a depth greater than 6 feet. The first 30 feet of the dam from the left abutment is battered at 3V:1H with stone. The dam foundation is bedrock which is visible immediately downstream of the toe for the right two-thirds of the dam. This rock is thick bedded and in good condition.

The upstream earth embankment to the left of the spillway has a horizontal grass covered crest 8.6 feet wide. The upper 1.5 feet of the upstream face is a vertical wall of dry laid stone 2.5 feet wide. The portion of the upstream earth embankment adjacent to the spillway and right abutment is at the same elevation as spillway crest and slopes away from the stone masonry at 1V:8H. Weeds are growing along the upstream side of crest and 4 to 8 inch diameter trees are growing at the embankment and abutment junctions. Two cables and one strand of barbed wire with a maximum height of three feet are supported on iron posts along the upstream limit of the crest.

Clear seepage is flowing at approximately 2 gpm from the downstream face about four feet below the crest and four feet to the right of the spillway. A pile of recently cut brush and small tree limbs obscures this area of the downstream face. Immediately downstream of the toe at the left end of the dam is an area of standing water. It is apparent from the type of vegetation that this area is usually wet. Inspection reports beginning in 1938 note that some seepage was observed at the right abutment and at the hillside on the left abutment. The area downstream of the toe of the overflow section is submerged by tailwater.

C. Appurtenant Structures

The spillway consists of a concrete capped overflow section of the dam 66 feet long, 7.4 feet wide and 1 foot deep. The concrete cap is 10 inches thick and has some spalling and surface erosion but no apparent structural defects. The approach channel is the reservoir with the bottom sloping at 1V:8H. Obstructions to flow are limited to the weeds and cables mentioned above. The downstream channel of the spillway consists of the vertical drop from the crest to the bedrock toe and a clear channel on bedrock for the full width of the spillway for the first 100 feet before narrowing to 10 feet wide. The channel immediately enters a shallow pond. The abandoned 2.5 foot high by 2.0 foot wide sluiceway in the left end of the dam is filled loosely with stones on the downstream side and is reportedly blocked on the upstream end by the stone masonry and earth embankment. No functional facility exists for drawing down the lake.

D. Reservoir Area:

About 25 per cent of the shoreline of the reservoir has residential development. The reservoir banks and the watershed are about 50% wooded and have flat to moderate slopes. The banks appear stable and major siltation is not expected.

E. Downstream Channel:

The downstream channel is tree lined with a flat slope. The first obstruction downstream is a road crossing about 1,500 feet downstream of the

dam. Approximately 4,000 feet from the dam another road crosses and one house is adjacent to the stream. Three more minor roads are crossed before reaching the Town of Varden 3.0 miles downstream of the dam. Four homes are located within the floodplain at this point. The proximity of these homes to the stream creates a high hazard to loss of life if the dam fails.

F. Evaluation

The visual inspection of Lake Quinn indicates that the dam and spillway are in fair condition. Maintenance is required to remove existing trees and brush from the embankment and abutments. Adequate drawdown facilities should be provided.

SECTION 4

OPERATIONAL PROCEDURES

4.1 Normal Operating Procedure

The facility is essentially self-regulating. Excess inflow passes through the emergency spillway located in the center of the dam. Inflows in excess of the emergency spillway capacity will overtop the concrete capped dry stone masonry embankment. No formal operations manual exists.

4.2 Maintenance of Dam

The condition of the dam as observed by the inspection team was fair. Basic maintenance such as keeping the spillway clear, and repairing minor flood damage is performed by the owner. No formal maintenance manual exists.

4.3 Maintenance of Operating Facilities

See Section 4.2 above

4.4 Warning System

No formal warning system exists.

4.5 Evaluation

Routine maintenance of the facility should include removal of trees and brush. No means currently exist to lower the elevation of the lake if required for any repair to part of the structure. Formal manuals of maintenance and operation are also recommended to ensure that all needed maintenance is identified and performed regularly. In addition, a formal warning system for the protection of downstream inhabitants should be developed. Included in the plan should be provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.

SECTION 5

HYDROLOGIC/HYDRAULIC EVALUATION

5.1 Design Data

No formal design reports, calculations or miscellaneous design data are known to exist for the facility. However, in 1917 calculations were determined for the "equalizing effect" of Lake Quinn on a proposed change to a downstream structure. Data developed in that report was filed in Harrisburg, PA, April 19, 1917.

5.2 Experience Data

Records of reservoir levels and/or spillway discharges are not available. Discussion with the owner indicated that the dam had been overtopped by up to 2.5 feet during two previous flood events in October 1955 and June 1972. Other overtoppings are not known and are considered to be less significant than these events. No other records of past performance are known to exist.

5.3 Visual Observations

On the date of the inspection, no conditions were observed that would prevent the facility from operating within the capability of the structure.

5.4 Method of Analysis

The facility has been analyzed in accordance with procedures and guidelines established by the U.S. Army, Corps of Engineers, Baltimore District for Phase I hydrologic and hydraulic evaluations. This analysis has been performed using a modified version of the HEC-1 program developed by the U.S. Army Corps of Engineers, Hydrologic Engineering Center Davis, California. Capabilities of the program are briefly outlined in the preface contained in Appendix D.

5.5 Summary of Analysis

a. Spillway Design Flood (SDF). In accordance with the procedures and guidelines contained in the National Guidelines for Safety Inspection of Dams for Phase I Investigations, the SDF for Lake Quinn ranges between one-half the Probable Maximum Flood (PMF) and the full PMF. This classification is based on the relative size of the dam (small), and the potential hazard of dam failure to downstream development (High). Due to the small storage (approximately 300 ac-ft) and small dam height (12.2 feet) the SDF selected was the one-half PMF.

b. Results of the Analysis. Lake Quinn was evaluated under near normal operating conditions. The starting lake elevation was set at spillway crest, elevation 1352. The emergency spillway consists of a 1 foot deep notch, 66 feet in length, in the center portion of the dam. Flood hydrographs were developed and the following results were obtained:

Spillway Capacity at Top of Dam	200 CFS
Peak PMF Inflow	16,440 CFS

The overtopping analysis (using HEC-1DB) indicated that the discharge/storage capacity of Lake Quinn can only accommodate 3% of the PMF. Under one-half PMF conditions, the dam is overtopped 30 hours to a maximum depth of 5.7 feet. Since the SDF for this dam is the one-half PMF, it can be concluded that Lake Quinn has a high potential for overtopping, and thus, for breaching under floods of less than SDF magnitude.

Included in this study was the effect of two upstream structures, Robinson Pond and Bronson Pond. These structures have been investigated in the Dam Safety Inspection program and have the following Pennsylvania DER numbers.

Robinson Pond	70-64-136
Bronson Pond	70-64-42

Flood routings for their subareas were used in this study as shown in Appendix D of this report.

The effect of Telshaw Pond, also located upstream, was considered to be insignificant for the purposes of this analysis.

To determine if the spillway is seriously inadequate, these conditions must be met:

(1) There is a high hazard to loss of life from large flows downstream of the dam.

(ii) The spillway is not capable of passing one-half PMF without overtopping the dam and causing failure.

(iii) Dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream of the dam from that which would exist just before overtopping failure.

Since Lake Quinn meets the first two conditions, a breach analysis was performed to determine whether the third condition is met.

The modified HEC-1 computer program was used for the breaching analysis. The computer program requires that the failure elevation be given to the model so that failure may commence. It was assumed that the dam could withstand up to 1.5 feet of overtopping for short durations. Therefore, the water surface elevation selected to cause failure would be elevation 1354.5.

Four breach models were analyzed under conditions that would approximate 1.5 feet of overtopping. The flood selected to cause breaching was 10% of the PMF. Of the four plans, Plan 1 was a non-breach analysis used to provide a means of direct comparison between failure and non-failure conditions at downstream locations for the same flood event. Failure times in the three remaining plans ranged were 0.33 hour (Plan 2), 1.00 hour (Plan 3), and 2.00 hours (Plan 4). Downstream damage elevations and locations are shown in Appendix D and E of this report. Page D-12 of Appendix D, provides peak outflows and changes in stage at the downstream damage centers and their

relationships between the four plans. As indicated in the table, failure conditions significantly increase the hazard to loss of life when compared to non-failure conditions. Breach geometry and location are also discussed in Appendix D.

5.6 Spillway Adequacy

Under existing conditions Lake Quinn can accommodate only 3% of the PMF. Should an event in excess of this occur, the dam would be overtopped and could possibly fail. Since the failure of this dam could lead to an increased hazard to loss of life or property damage at existing downstream residences, this spillway is considered seriously inadequate.

SECTION 6

STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

1. Embankment. Visual observations of the Lake Quinn Dam indicate that the dam is in fair condition. The dam is a dry laid stone structure with an overflow spillway section and a random earth embankment upstream. The stone structure is 7.4 feet wide, has a 10-inch thick concrete cap, and has a vertical downstream face, except on the downstream left end. Additional stone for a length of 30 feet has been added to the downstream face of the dam at the left abutment. It is battered at a slope of 1H:3V. The upstream earth embankment to the left of the spillway has a horizontal crest 8.6 feet wide and a vertical upstream dry laid stone face approximately 1.5 feet high by 2.5 feet wide. The embankment crest upstream of the spillway and right abutment is at spillway elevation and slope away from the stone structure at an 8H:1V slope. Clear seepage estimated at 2 gpm was observed at the right abutment contact. At the left downstream toe, stagnant water was observed; it appeared from the vegetation that this area is usually wet. Inspection reports as early as 1938 mentioned that seepage was observed at the right abutment and from the hillside at the left abutment.

The base of the dam and right abutment are founded on bedrock of siltstone and shale. The left downstream abutment may have undergone some minor settlement or movement in the rock structure as evidenced by a crack in a patch of mortar. Brush has been dumped on the left downstream abutment and weeds are growing on it which prohibit a thorough inspection of this area.

2. Appurtenant Structures. The spillway is an overflow section of the dam, 66 feet long, 12 inches deep, and 7.4 feet wide. It is capped by a 10-inch thick concrete slab. Upstream of the spillway the earth embankment slopes away at 8H to 1V. An abandoned sluiceway 2.5 feet high by 2 feet wide was observed to exit near the left abutment. The sluiceway should be filled and grouted to prevent a possible collapse as the timbers in it are rotten.

b. Design and Construction Data

1. Embankment. There are no known design or construction data for this dam. The dam originally consisted of a vertical faced dry laid stone structure and had no upstream embankment. Timber planks were used on the upstream face for an impervious barrier. A few pictures dated from 1915 to the 1930's show that large capstones were placed on the crest of the dam and timber planking was placed on the spillway crest. Profile, cross section and plan view sketches of the dam are available for the changes proposed in 1946, some of which have been made. These sketches indicated that stone would be placed against the downstream dam face at a slope of 2H:3V; the crest would be capped with 6 inches of concrete; and an upstream embankment would be added with a 12 foot horizontal crest and an upstream slope of 2 1/3H:3V.

2. Appurtenant Structures. No design or construction data are known to exist other than the rough sketches mentioned above.

c. Operating Records. There are no records of operation.

d. Post-Construction Changes. Dam length was increased sometime between 1946 and 1965. An upstream earth embankment was added, and additional stone was laid at the left abutment. An upstream clay blanket was also added in the early 70's.

e. Seismic Stability The dam is located in Seismic Zone 1. Based on visual observations, the static stability of the dam is considered to be adequate. The seismic stability of the dam is therefore considered to be adequate.

SECTION 7

ASSESSMENT AND RECOMMENDATIONS

7.1 DAM ASSESSMENT

A. Safety

The visual inspection and review of available design and construction information indicate that Lake Quinn Dam is in fair condition. Deficiencies noted during the inspection included the lack of functional drawdown facilities and minor seepage through the masonry near the right abutment.

The hydrologic and hydraulic computations indicate that the combination of reservoir storage and spillway discharge capacity will pass only 3 percent of the PMF without overtopping the dam. Therefore, in accordance with criteria outlined and evaluated in Section 5.5b, the spillway for Lake Quinn Dam is considered to be seriously inadequate, and the dam is judged to be unsafe, non-emergency.

B. Adequacy of Information

The available information contained in PennDER files, in conjunction with data collected during the visual inspection, are considered to be adequate for making a reasonable assessment of this dam.

C. Urgency

The recommendations presented below should be implemented immediately.

D. Necessity for Additional Studies

The results of this inspection indicate a need for additional studies to further assess the adequacy of the spillway and develop necessary plans for providing adequate spillway capacity.

7.2 RECOMMENDATIONS

It is recommended that the owner immediately:

A. Retain a qualified professional engineer to perform a detailed hydrologic and hydraulic study to further assess the discharge capacity of the spillway and develop remedial measures found necessary to provide adequate spillway capacity. This study should also include development of an adequate drawdown facility for the dam having positive upstream closure capability.

B. The existing sluiceway should be sealed, unless rehabilitation is undertaken.

C. The seepage, near the right abutment should be monitored and appropriate remedial action taken should the condition begin to worsen significantly.

D. Remove trees and brush from the abutments, and the cable and wire from the upstream face of the dam.

E. A formal surveillance and downstream emergency warning system should be developed for use during periods of heavy or prolonged precipitation.

F. An operation and maintenance manual or plan should be prepared for use as a guide in the operation of the dam during normal and emergency conditions.

G. A schedule of regular inspections by a qualified engineer should be developed.

APPENDIX A

CHECKLIST - VISUAL INSPECTION

Check List
Visual Inspection
Phase I

Name Dam Lake Quinn Dam County Wayne State Pennsylvania

Date(s) Inspection 4 Nov 80 Weather Cloudy Temperature 50°

Pool Elevation at Time of Inspection 1352.1 M.S.L. Tailwater at Time at Inspection 1341.2 M.S.L.

Inspection Personnel:

J. Bianco (C.O.E.)

E. Hecker (C.O.E.)

David Beynon, Sr., Owner

B. Cortright (C.O.E.)

J. Evans (C.O.E.)

B. Cortright Recorder

STONE MASONRY AND EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS
CREST ALIGNMENT:	
1. Horizontal	1. Horizontal - Good
2. Vertical	2. Vertical - Good except for slight settlement at downstream side of left abutment
SURFACE CRACKS:	
Concrete	Concrete cap is cracked and spalling in several locations
Embankment	D/S slope of earthfill was submerged. Crest good. No cracks observed.
STRUCTURAL CRACKING	None
FUNCTION OF EMBANKMENT WITH:	
Abutments	Slight settlement of downstream side of left abutment; otherwise good.
Spillway	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None.
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None.

FOUNDATION	Bedrock; exposed at toe of spillway and right end and in downstream channel.
RIPRAP	No riprap.
ANY NOTICEABLE SEEPAGE	Approximately 2 gpm of clear water is flowing from d/s face; about 4 feet right of spillway and 4 feet below crest. A wet area exists about 7 feet d/s of toe and 30 feet from the left abutment. Flow over spillway and tailwater obscured a portion of d/s face and toe.
STAFF GAUGE & RECORDER	None.
INSTRUMENTATION	None.
MISCELLANEOUS	<p>Trees at the right and left abutments. Weeds along u/s face. 2 cables & 1 strand barbed wire stretched across u/s face; supported on iron posts 1' & 3' above crest.</p> <p>The old sluiceway (2' x 2.5' high) is loosely filled with stones and timber; probed more than 6 feet from d/s face; no seepage.</p>

SPILLWAY

OBSERVATIONS

at a critical notch in top of dam. Some surface cracking and spalling.
No rolling.

Deep water, holes and 1 strand barbed wire on iron posts along u/s edge,
1 foot high. One-third of u/s area is full of grass and weeds -
1 foot high.


Water level 1.5 ft. until narrowing to 10 feet wide 10 feet d/s of
dam. Steepening sides at narrowest point. Then widest to 70' wide pool.

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS
SLOPES	Flat to moderate; no potential for massive slide
SEDIMENTATION	None observed.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS
CONDITION: Obstructions Debris Other	Several road crossings before reaching the town of Varden.
SLOPES: Channel Sides	Flat Flat to LV on 2H
APPROXIMATE NUMBER OF JOMS	One house - 4,000 feet downstream. Four homes in Varden 3.0 miles downstream.



2 GPM

INDICATES LOCATION AND
QUANTITY OF SEEPAGE

NOT TO SCALE


PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

LAKE QUINN DAM

DAVID BEYNON, SR


FIELD SKETCH

EXHIBIT A-1



TOP OF DAM - PROFILE

HORIZ.: 1 IN. = 20 FT.
SCALE - VERT.: 1 IN. = 2 FT.



PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

LAKE QUINN DAM

DAVID BEYNON, SR

PROFILE AND SECTIONS

EXHIBIT A-2

APPENDIX B

CHECKLIST - ENGINEERING DATA

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE I

NAME OF DAM Lake Quinn Dam
NDI ID # PA 00145
DER ID # 64-43

ITEM

REMARKS

As-Built Drawings

None.

Regional Vicinity Map

U.S.G.S. Waymart Quadrangle - 7 1/2 minute Quad Sheet. See Appendix E, Plate E-Z.

Construction History

Original Embankment completed prior to 1917. Modifications have been made since that time.

Typical Sections of Dam

None.

Outlets - Plan
Details
Constraints
Discharge Ratings

None.

Rainfall/Reservoir Records

None.

Design Reports

None.

Geology Reports

None.

ITEMREMARKS

Design Computations Hydrology & Hydraulics Dam Stability Seepage Studies	In 1917 a report was filed to the state for a proposed change at a downstream structure, W.W. Kiser's Dam (File No. 64-46) 2.75 miles downstream of Lake Quinn Dam. This report included in its study the equalizing potential of Lake Quinn Dam on this downstream structure.
Materials Investigations Boring Records Laboratory Field	None.
Post-Construction Surveys of Dam	None.
Monitoring Systems	None.
Modifications	Dam lengthened and reinforced by placing random fill on upstream face, sluiceway constructed in old Millrace sometime after 1946 and before 1965.
High Pool Records	In 1955 and 1972 flows reached a depth of overtopping the embankment up to 2.5 feet.
Post-Construction Engineering Studies and Reports	Sometime between 1946 and 1965 modifications above were accomplished. A clay blanket was placed on the upstream face in early 1970's to stop leakage through the dam.
Prior Accidents or Failure of Dam Description Reports	None reported.

ITEM

REMARKS

Maintenance
Operation
Records

None.

Spillway Plan

Sketch in Appendix A.

Sections
Details

Operating Equipment
Plans & Details

None.

Specifications

None.

Miscellaneous


None.

Previous Inspections

1965 (PennDER) latest, others in 1952, 1948, 1938, 1935, 1932, 1930,
1928, 1924 by State Personnel.


APPENDIX C

PHOTOGRAPHS






1. Overview of Dam.



2. Upstream from Rehabilitation.



3. Crest and Left Abutment.



4. Downstream Face adjacent to right abutment.



CLIFF, WEST OF P.



APPENDIX D

HYDROLOGY AND HYDRAULICS

PREFACE

The modified HEC-1 program is capable of performing two basic types of hydrologic analyses: 1) the evaluation of the overtopping potential of the dam; and 2) the estimation of the downstream hydrologic-hydraulic consequences resulting from assumed structural failures of the dam. Briefly, the computational procedures typically used in the dam overtopping analysis are as follows:

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir to determine if the event(s) analyzed would overtop the dam.
- c. Routing of the outflow hydrograph(s) from the reservoir to desired downstream locations. The results provide the peak discharge(s), time(s) of the peak discharge(s), and the maximum stage(s) of each routed hydrograph at the downstream end of each reach.

The evaluation of the hydrologic-hydraulic consequence resulting from an assumed structural failure (breach) of the dam is typically performed as shown below.

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir.
- c. Development of a failure hydrograph(s) based on specified breach criteria and normal reservoir outflow.
- d. Routing of the failure hydrograph(s) to desired downstream locations. The results provide estimates of the peak discharge(s), time(s) to peak and maximum water surface elevations of failure hydrographs for each location.

HYDROLOGY & HYDRAULIC ANALYSIS
DATA BASE

NAME OF DAM: LAKE QUINN DAM

PROBABLE MAXIMUM PRECIPITATION (PMP) = 21.5 INCHES/24 HOURS (1)

DELAWARE RIVER BASIN

STATION	1	2	3
STATION DESCRIPTION	ROBINSON POND DAM	BROOKS POND DAM	LAKE QUINN DAM
DRAINAGE AREA (SQUARE MILES)	0.50	2.38	6.86
CUMULATIVE DRAINAGE AREA (SQUARE MILES)	0.50	2.38	9.74
ADJUSTMENT OF PMF FOR (1) DRAINAGE AREA LOCATION (%)	ZONE 1	ZONE 1	ZONE II
6 Hours	111	111	111
12 Hours	123	123	123
24 Hours	133	133	133
48 Hours	142	142	142
72 Hours	-	-	-
SNYDER HYDROGRAPH PARAMETERS			
Zone (2)	1	1	1
C _p (3)	0.45	0.45	0.45
C _t (3)	1.23	1.23	1.23
L ^t (MILES) (4)	1.04	2.72	7.55
L _{ca} (MILES) (4)	0.52	1.33	1.84
tp = C _t (L ^t + L _{ca}) 0.3 (HOURS)	1.02	1.85	2.35
SPILLWAY DATA		ROCK FILL DAM	
CREST LENGTH (FEET)	12	N/A	66
FREEBOARD (FEET)	1.2	N/A	1.0

(1) HYDROMETEOROLOGICAL REPORT - 33, U. S. Army Corps of Engineers, 1955.

(2) Hydrologic zone defined by Corps of Engineers, Baltimore District, For Determination of Snyder Coefficients (C_p and C_t).

(3) Snyder Coefficients

- (4) L = Length of longest watercourse from dam to basin divide.
L_{ca} = Length of longest watercourse from dam to point opposite basin centroid.

SUBJECT DAM SAFETY INSPECTIONCOMPUTATIONS LAKE QUINN SHEET 1 OF 13 SHEETSCOMPUTED BY JPS CHECKED BY _____ DATE 6-12-80DAM CLASSIFICATION

SIZE OF DAM - SMALL

HAZARD - HIGH

REQUIRED FDC - 1/2 PMF TO FULL PMF

DAM STATISTICS

HEIGHT OF DAM - 12.2 FT.

STORAGE AT NORMAL POOL - 190 AC-FT (FROM REMOVED FLOOD)

STORAGE AT TOP OF DAM - 305 AC-FT

DRAINAGE AREA ABOVE DAM SITE - 9.74 mi.² (TOTAL)ELEVATIONS *

TOP OF DAM (LOW POINT) - 1353.0

NORMAL POOL - 1352.0

SPILLWAY CREST - 1352.0

STREAMBED AT CENTERLINE OF DAM - 1340.8

HYDROGRAPH PARAMETERS

RIVER BASIN - DELAWARE

ZONE - 1

CYNDERS COEFFICIENTS -

 $C_p - 0.45$ $C_L - 1.23$

MEASURED PARAMETERS - DETERMINED FROM U.S.G.S.

WAYMART, PA. QUAD SHEET

L = LENGTH OF THE LONGEST WATERCOURSE: $L = 5.38 \text{ mi}$ LCA = LENGTH OF THE LONGEST WATERCOURSE TO CENTROID OF THE BASIN: $LCA = 2.08 \text{ mi}$ FOR FUTURE
WATERCHED?* DRAINAGE TOTAL
AREA TO THE
DAM SITE
(15.12 SQ. MILES)

* ELEVATIONS ARE REFERENCED TO U.S.C. QUAD SHEET WAYMART, PA. GUIDING LAKE ELEVATION AT 1352 ASSUMED TO BE AT SPILLWAY CREST.

SUBJECT DAM SAFETY INSPECTIONCOMPUTATIONS LAKE QUINNSHEET 13 OF 13 SHEETSCOMPUTED BY JK CHECKED BY _____ DATE 1-12-80

NOTE: 3 STRUCTURES ARE UPSTREAM OF LAKE QUINN. ROBINSON POND AND BRONSON POND ARE LARGE ENOUGH TO INCLUDE STORAGE EFFECTS. THE THIRD STRUCTURE, TELSHAW POND HAS A VERY SMALL HEIGHT (LESS THAN 6 FEET) AND STORAGE (LESS THAN 100 AC-FT). THEREFORE, ROBINSON AND BRONSON POND WILL BE INCLUDED UPSTREAM OF LAKE QUINN, BUT TELSHAW POND WILL BE IGNORED.

MEASURED PARAMETERS FOR UNCONTROLLED AREA
ABOVE LAKE QUINN

$$L = 4.55 \text{ mi}$$

$$L_{CA} = 1.89 \text{ mi}$$

TOTAL DRAINAGE AREA IS 9.74 mi^2

UNCONTROLLED DRAINAGE AREA ABOVE LAKE QUINN = 6.86 mi^2

t_p = SYDERS BASIN LAG TIME TO PEAK IN HOURS

FOR UNCONT
AREA

$$t_p = C_t (L L_{CA})^{0.3}$$

$$= 1.23 (4.55 (1.89))^{0.3}$$

$$= 2.25 \text{ hours}$$

RESERVOIR CAPACITY

- SURFACE AREA AT NORMAL POOL (ELEV. 1352) = 154 ACRES

- SURFACE AREA AT ELEVATION 1360 = 250 ACRES


ASSUME CONICAL METHOD APPLIES TO FIND
LOW POINT IN POOL, BELOW NORMAL POOL.

VOLUME AT NORMAL POOL = 110 AC-FT.
(FROM TEASDER FILES)

* VALUES PLAINIMETERED BY WAYMART & LAKE ARIEL, VA.
ROAD SHEETS. WAYMART PLAINIMETERED 1969 LAKE ARIEL 1966 SERIES.

SUBJECT DAM SAFETY INSPECTIONCOMPUTATIONS LAURENCE (JUNIOR)SHEET 2 OF 15 SHEETSCOMPUTED BY J.P.B. CHECKED BY _____ DATE 2-10-80FROM CONICAL METHOD: $V = \frac{1}{3}Ah$ $A = \pi r^2 = 104 \text{ ACRES}$

$$\therefore h = \frac{3V}{A} = \frac{3(190 \text{ AC-FT})}{104 \text{ AC}} = 5.5 \text{ FT.}$$

ELEVATION WHERE $V=0$, $1352.55 = 1346.5$ ELEVATION - STORAGE TABLE

ELEVATION (MSL)	AREA (AC)	Δh (FT)	$\Delta V = \Delta h \left(\frac{A_1 + A_2}{2} \right)$ (AC-FT)	CUMULATIVE VOLUME (AC-FT)
1346.5 ^(B)	0		190 (conical method)	0
1352.0	104	1.0	115	190
1353.0 (Top)	125	1.0	138	~305
1354.0	150	1.0	166	~445
1355.0	182	1.0	198	~610
1356.0	213	1.0	229	~810
1357.0	245	1.0	263	~1040
1358.0	280	1.0	298	~1300
1359.0	315	1.0	332	~1600
1360.0	350			~1930

THE ABOVE ROUTINE PROCEDURE ASSUMES THE DAM AREA IS A CONICAL METHOD

IS ADJUSTED TO ELEVATIONS ABOVE SEILMAN CREST 1352.0.

(B) NOTE - ELEVATION 1346.5 IS ABOVE THE INVERT OF THE DAM (EL. 1340 B)

HACB 10-4-23, 28 MAR 74

SUBJECT DAM SAFETY INSPECTION

COMPUTATIONS

LAKE QUAKO

SHEET

13

COMPUTED BY

JCF

CHECKED BY

DATE

PMF CALCULATIONS:

- APPROXIMATE RAINFALL INDEX = 21.5 INCHES
(CORRESPONDING TO A DURATION OF 24 HOURS AND A
DRAINAGE AREA OF 200 mi^2) - ALL SEASON ENVELOPE
- LENGTH-AREA DURATION ZONE 1 : FROM HYDROMET # 33
- ASSUME VALUES CORRESPONDING TO 10 mi^2 AREA MAY BE
APPLIED TO THIS 9.74 mi^2 BASIN

<u>DURATION (HRS)</u>	<u>PERCENT OF INDEX RAINFALL</u>
6	111
12	123
24	133
48	142

NOTE: HOP BROOK FACTOR IS INTERNALLY COMPUTED BY THE HECDB PROGRAM. FOR A DRAINAGE AREA LESS THAN 10 SQUARE MILES THE ADJUSTMENT FACTOR IS 1.0. THE ADJUSTMENT IS FOR BASIN SHAPE AND FOR THE DESIGN DURATION OF A SEVERE STORM CENTERING OVER A SMALL BASIN.

SDF:

BASED ON THE SMALL HEIGHT OF DAM (20 FEET) AND THE SMALL STORAGE AT LOW TOP OF DAM (~305 AC FT), THE SDF SELECTED FOR A HIGH HAZARD AND SMALL SIZE IS $\frac{1}{2}$ PMF.

\therefore USE SDF = $\frac{1}{2}$ PMF

EMERGENCY SPILLWAY CAPACITY:


NOTE: SPILLWAY IS IN CENTER OF EMBANKMENT.

SEE FIELD SKETCH IN APPENDIX A EXHIBIT A-1

WIDTH OF SPILLWAY IS 200 FT - HORIZONTAL CENTER LINE

SUBJECT DAM SAFETY INSPECTIONCOMPUTATIONS LAKE QUINNSHEET 1 OF 12 SHEETSCOMPUTED BY JPB

CHECKED BY _____

DATE 12-16-74

NOTE: SPILLWAY IS 16 FT IN
LENGTH AND 1 FT
DEEP.

∴ BROAD CRESTED WEIR.

$$Q = CLH^{3/2}$$

where L = length of weir 66'

H = height over weir max 1'

before over EMBANKMENT

C = WEIR COEFFICIENT = 2.85

SPILLWAY RATING CURVE:

POOL ELEVATION (MSL)	H (FT)	Q (CFS)	ROUTED Q (CFS)
1352	0	0	0
1353	1	187	190
1354	2	532	530
1355	3	977	980
1356	4	1504	1500
1357	5	2102	2100
1358	6	2763	2760
1359	7	3483	3480
1360	8	4255	4260

(CONTINUED)

POOL ELEV. (MSL)	H (FT)	Q (CFS)	ROUTED Q (CFS)
1370	18	14365	14360

EMBANKMENT RATING CURVE:

THIS ANALYSIS ASSUMES THAT THE EMBANKMENT BEHAVES AS A BROAD CRESTED WEIR IF OVERTOPPING OCCURS. THE DISCHARGE CAN BE ESTIMATED BY:

$$Q = CLH_w^{3/2}$$

where: Q = DISCHARGE OVER EMBANKMENT, IN CFS

L = LENGTH OF EMBANKMENT, FT

H_w = WEIGHTED HEAD IN FEET, AVERAGE FLOW AREA WEIGHTED ABOVE LOW POINT OF DAM

C = COEFFICIENT OF DISCHARGE

SUBJECT LAKE SAFETY INSPECTIONCOMPUTATIONS LAKE GUINNSHEET 6 OF 13 SHEETSCOMPUTED BY JPB

CHECKED BY _____

DATE 12-17-80

LENGTH OF EMBANKMENT INUNDATED
VS. RESERVOIR ELEVATION :

RESERVOIR ELEVATION (MSL)EMBANKMENT LENGTH (ft)

1352.0	0
1353.0	0
1354.0	80
1355.0	100
1356.0	110
1357.0	115
1358.0 *	120
1359.0 *	120
1360.0 *	120

* 120 FT - MAXIMUM LENGTH OF EMBANKMENT PLUS SOME
 ABUTMENT LENGTH C=2.85

EMBANKMENT RATING TABLE

RESERVOIR ELEVATION (MSL)	L ₁ (ft)	L ₂ (ft)	INCREMENTAL HEAD H _i (ft)	① INCREMENTAL FLOW AREA A _i (ft ²)	TOTAL FLOW AREA (ft ²) A _T	② WEIGHTED HEAD H _w (ft)	③ Q (CF)
1352.0	0	-	-	-	-	-	0
1353.0	0	0	1.0	0	0	0	0
1354.0	80	0	1.0	40	40	0.50	80
1355.0	100	80	1.0	90	130	1.30	421
1356.0	110	100	1.0	105	235	2.14	981
1357.0	115	110	1.0	112.5	347.50	3.02	1720
1358.0	120	115	1.0	117.5	465.0	3.88	2613
1359.0	120	120	1.0	120	585.0	4.88	3686
1360.0	120	120	1.0	120	705.0	5.88	4376
1370.0	120	120	10.0	200	1905.0	15.88	21640

$$① A_i = H_i [(L_1 + L_2) / 2]$$

$$② H_w = A_i / L_1$$

$$③ Q = CL_1 H_w^{3/2}$$

SUBJECT DAM SAFETY EXPECTATIONCOMPUTATIONS LAKE CRUMER SHEET 7 OF 13 SHEETSCOMPUTED BY JPC CHECKED BY _____ DATE 12-1-57TOTAL FACILITY RATING CURVE


$$Q_{TOTAL} = Q_{SPILLWAY} + Q_{EMBANKMENT}$$

RESERVOIR ELEV. (FT)	Q SPILLWAY (CFS)	Q EMBANKMENT (CFS)	Q TOTAL (CFS)
1352.0	0	0	0
1353.0	190	0	190
1354.0	530	80	610
1355.0	980	420	1400
1356.0	1500	980	2480
1357.0	2100	1720	3320
1358.0	2760	2610	5370
1359.0	3480	3670	7170
1360.0	4260	4810	9040
1370.0	14360	21640	36000

VALUES TO BE INPUT ON 1/4 & 1/5 CARDS.

RESULTS OF THE OVERTOPPING ANALYSIS

FROM THE OVERTOPPING ANALYSIS THE FOLLOWING CURVE CAN BE DRAWN.



LOW POINT OF DAM IS 1353.0

POINTS PLOTTED FROM PAGE 21/21 OF THE OVERTOPPING ANALYSIS OF THIS APPENDIX.


∴ THE DAM AND SPILLWAY CAN ACCOMMODATE A FLOOD UP TO 3% PMF PRIOR TO OVERTOPPING THE EMBANKMENT.

SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS LAKE QUINNSHEET 8 OF 13 SHEETSCOMPUTED BY JAB CHECKED BY _____ DATE 12-22-80

SINCE THIS DAM IS A HIGH HAZARD, AND IT IS FELT THAT THE 50% PMF WOULD CAUSE FAILURE A BREACH ANALYSIS IS REQUIRED. THE BREACH ANALYSIS WOULD EXAMINE THE SIGNIFICANCE OF FAILURE AND NON-FAILURE CONDITIONS FOR $\sim 10\%$ PMF.

BREACH ANALYSIS:

TYPICAL BREACH SECTION



PAST HISTORICAL EVENTS HAVE BEEN KNOWN TO OVERTOP THE EMBANKMENT BY AS MUCH AS 2.5 FEET. THIS OCCURED DURING THE OCT. 1955 & JUNE 1972 EVENTS. SINCE THE EMBANKMENT IS CONCRETE CAPPED AND HAS A RUBLE STONE DOWNSTREAM FACE, IT WAS FELT THAT A $1\frac{1}{2}$ FOOT OF OVERTOPPING FOR A SHORT DURATION COULD BE WITHSTOOD. THEREFORE, FOR THE BREACHING ANALYSIS, 10% OF THE PMF WOULD BE APPROPRIATE FOR THIS ANALYSIS.

HEC1AB INPUT PARAMETERS FOR BREACH ANALYSIS

FOUR PLANS WILL BE USED FOR A DIRECT COMPARISON OF FAILURE VS. NON-FAILURE CONDITIONS. PARAMETERS ARE AS FOLLOWS.

PLAN NUMBER	BREACH BOTTOM WIDTH (FT)	FULL BREACH DEPTH (FT)	SIDE SLOPES	TOTAL BREACH TIME (HR)
1	—	—	non failure	—
2	66	9	0.5H:1V	0.33
3	66	9	0.5H:1V	1.00
4	66	9	0.5H:1V	2.00

SUBJECT DAM SAFETY ANALYSISCOMPUTATIONS LAKE QUINNSHEET 7 OF 13 SHEETSCOMPUTED BY JPB

CHECKED BY

DATE 10 22-80HEC1-DB OUTPUT

RESULTS OF DAM BREACH ANALYSIS

AS NOTED FROM PAGE D-11, PLAN 1 IS FOR NON-FAILURE CONDITIONS.

PLAN NUMBER	MAXIMUM OUTFLOW OVER DAM AND/OR THRU BREACH (CFS)	DOWNSTREAM DAMAGE CENTER #1		DOWNSTREAM DAMAGE CENTER #2	
		STAGE (MSL)	FLOW (CFS)	STAGE (MSL)	FLOW (CFS)
1	1100	1323.4	1100	1234.1	1090
2	7000	1331.6	7610	1239.9	5860
3	6800	1330.4	6180	1239.4	5220
4	5560	1329.6	5280	1238.9	4600

DOWNSTREAM DAMAGE CENTER #1 - DAMAGE ELEV. AT 1332.0

DOWNSTREAM DAMAGE CENTER #2 - DAMAGE ELEV. AT 1238.0

FROM THE TABLE ABOVE, IT CAN BE SEEN THAT AT THE LOWER
DOWNSTREAM DAMAGE CENTER #2, FAILURE SIGNIFICANTLY
INCREASES DOWNSTREAM HAZARD POTENTIAL.

SAFETY ANALYSIS

COMPUTATIONS AND QUANTA

SHEET

3

SHEET

COMPUTED BY


MC

CHECKED BY

DATE


5 51

COMPUTER MODEL - LOW CHART




THIS SKETCH IS A
BREAKDOWN OF INPUT
VARIABLES TO MODEL.

NUMBERS REFER TO COMPUTER VALUES IN INPUT PROGRAM



Notes: ~500 ft. DOWNSTREAM OF DAM 1st 100 ft. Dikes
are ~5 ft. above T.O.D. at LAKE QUINCY

LAKE QUINCY
CROSS SECTION APPROXIMATELY 10' 11"
DOWNSTREAM OF DAM




LAKE QUINN
DOWNSTREAM X-SECTION INTERIM
4000 FT. DOWNSTREAM FROM
DAM CENTER #1

LOOKING DOWNSTREAM

NOTE THIS DAM CENTER IS 200 FT. DOWNSTREAM
OF 20 FT. HIGH BY 30 FT. WIDE
HIGHWAY CULVERT

PLAN 2 - BREACH CONDITION PEAK
WATER SURFACE ELEVATION



LAKE QIMMUN

NOTE: THIS DAMAGE CENTER IS IMMEDIATELY DOWNSTREAM
OF TWO DAMS:

- ~200' DOWNSTREAM OF DER # 10 C-1-45 (WATER POWER DAM)
- ~500' DOWNSTREAM OF DER # 10 C-1-47 (MILL POND DAM)

DOWNSTREAM X-SECTION APPROXIMATELY
4,500' DOWNSTREAM OF DAM

THIS X-SECTION IS IN ARGENTINA.
DAMAGE CENTER #2

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 01 APR 80

1	A1	LAKE GUINN DAM DER NO. 90-64-43									
2	A2	DAM SAFETY INSPECTION PROGRAM 12-9-80									
3	A3	OVERTOPPING ANALYSIS *** PRELIMINARY ***									
4	R	144	0	20	0	0	0	0	0	-3	0
5	R1	5	0	0	0	0	0	0	0	0	0
6	J	1	6	1							
7	J1	0.01	0.10	0.20	0.30	0.50	1.00				
8	V	0	1	0	0	0	0	1	0	0	0
9	K1	RUNOFF FROM DRAINAGE AREA ABOVE ROBINSON DAM									
10	M	1	1	0.50	0	9.74	0	0	0	1	0
11	P	0	21.5	111	123	133	142				
12	T	0	0	0	0	0	0	1.0	0.05	0	0
13	W	1.02	0.45								
14	X	-1.5	-0.05	2							
15	K	1	1	0	0	0	0	1	0	0	0
16	K1	ROUTING XPM'S THRU ROBINSON DAM AND SPILLWAY									
17	V	0	0	0	1	1	0	0	0	0	0
18	V1	1	0	0	0	0	0	-1643	-1	0	0
19	Y4	1643.0	1643.5	1644.2	1644.5	1645.0	1646.0	1650.0	1655.0		
20	V5	0	12.0	45.0	90.0	390.0	1570.0	12030.0	37000.0		
21	SS	0	150	190	410	660	960				
22	SE	1627.7	1643.0	1644.2	1650.0	1655.0	1660.0				
23	SE	1643.0									
24	SD	1644.2									
25	K	1	2	0	0	0	0	1	0	0	0
26	K1	DOWNSTREAM X-SECTION 230 FEET FROM DAM (ROBINSON)									
27	V	0	0	0	1	1	0	0	0	0	0
28	V1	1	0	0	0	0	0	0	0	0	0
29	V6	0.07	0.05	0.07	1622	1638	230	0.0090	0	0	0
30	V7	100	1638	142	1630	162	1625	175	1622	190	1622
31	V7	197	1625	207	1630	225	1638				
32	K	1	3	0	0	0	0	1	0	0	0
33	K1	ROUTE THRU THE 2ND DOWNSTREAM CROSS SECTION (ROBINSON)									
34	V	0	0	0	1	1	0	0	0	0	0
35	V1	1	0	0	0	0	0	0	0	0	0
36	V6	0.07	0.05	0.07	1620	1638	270	0.0090	0	0	0
37	V7	100	1638	140	1627.8	180	1627	192	1620	202	1620
38	V7	210	1627	277	1633.6	323	1638				
39	K	1	4	0	0	0	0	1	0	0	0
40	K1	ROUTE FLOW THRU 3RD DOWNSTREAM CROSS SECTION (ROBINSON)									
41	V	0	0	0	1	1	0	0	0	0	0
42	V1	1	0	0	0	0	0	0	0	0	0
43	V6	0.07	0.05	0.07	1400	1414	8200	0.077	0	0	0
44	V7	100	1414	120	1406	170	1403	175	1400	178	1400
45	V7	185	1405	246	1406	270	1414				
46	K	1	5	0	0	0	0	1	0	0	0
47	K1	ROUTE FLOWS TO HEAD OF LAKE GUINN (FROM ROBINSON)									
48	V	0	0	0	1	1	0	0	0	0	0
49	V1	1	0	0	0	0	0	0	0	0	0
50	V6	0.07	0.05	0.07	1352	1380	4400	0.0109			
51	V7	100	1380	500	1360	700	1353	705	1352	905	1352
52	V7	910	1353	1200	1360	1400	1380				
53	K	0	6	0	0	0	0	1	0	0	0
54	K1	RUNOFF FROM DRAINAGE AREA ABOVE BRONSONS POND									
55	M	1	1	2.38	0	9.74	0	0	0	1	0
56	P	0	21.5	111	123	133	142				
57	T	0	0	0	0	0	0	1.0	0.05	0	0
58	W	1.85	0.45								
59	X	-1.5	-0.05	2							
60	K	1	6	0	0	0	0	1	0	0	0
61	K1	ROUTING XPM'S THRU BRONSONS POND									
62	V	0	0	0	1	1	0	0	0	0	0
63	V1	1	0	0	0	0	0	-1403	-1	0	0
64	Y4	1403.1	1403.2	1403.6	1404.0	1405.0	1410.0	1415.0	1420.0		
65	V5	0	0.5	23.0	95.0	520.0	5310.0	13300.0	23500.0		
66	SS	0	380	385	500	890	1490	2320			
67	SE	1382.0	1403.0	1403.1	1405.0	1410.0	1415.0	1420.0			
68	SE	1403.0									
69	SD	1403.1									

LAKE GUINN
 OVERTOPPING ANALYSIS
 PAGE 1/2

70	K	1	7	0	0	0	0	1			
71	K1	ROUTE FLOWS THRU 1ST DOWNSTREAM CROSS SECTION (BRONSON)									
72	Y	0	0	0	1	1	0	0			
73	Y1	1	0	0	0	0	0	0			
74	Y6	0.07	0.05	0.07	1393	1411	200	0.008			
75	Y7	100	1411	125	1405	136	1397	140	1393	180	
76	Y7	186	1397	190	1402	230	1411			1393	
77	K	1	8	0	0	0	0	1			
78	K1	ROUTE FLOWS THRU 2ND DOWNSTREAM CROSS SECTION (BRONSON)									
79	Y	0	0	0	1	1	0	0			
80	Y1	1	0	0	0	0	0	0			
81	Y6	0.07	0.05	0.07	1368	1400	3100	0.008			
82	Y7	100	1400	200	1380	250	1373	255	1368	285	
83	Y7	290	1372	350	1380	500	1400			1368	
84	K	1	9	0	0	0	0	1			
85	K1	ROUTE FLOWS TO HEAD OF LAKE QUINN (FROM BRONSON)									
86	Y	0	0	0	1	1	0	0			
87	Y1	1	0	0	0	0	0	0			
88	Y6	0.07	0.05	0.07	1357	1375	1000	0.011			
89	Y7	100	1375	106	1369	240	1362	280	1357	320	
90	Y7	323	1359	340	1369	356	1375			1357	
91	K	0	10	0	0	0	0	1	0	0	
92	K1	RUNOFF FROM UNCONTROLLED DRAINAGE AREA ABOVE LAKE QUINN									
93	M	1	1	6.86	0	9.74	0	0	1	0	
94	P	0	21.5	111	123	133	142				
95	T	0	0	0	0	0	0	1.0	0.05	0	
96	W	2.35	0.45								
97	X	-1.5	-0.05	2							
98	K	3	11	0	0	0	0	1			
99	K1	COMBINE 3 HYDROGRAPHS AT LAKE QUINN ROUTE COMBINED HYD. THRU LAKE									
100	K	1	12	0	0	0	0	1	0	0	
101	K1	ROUTING 12PF'S THRU LAKE QUINN									
102	Y	0	0	0	1	1	0	0	0	0	
103	Y1	1	0	0	0	0	0	-1352	-1	0	
104	Y4	1352.0	1353.0	1354.0	1355.0	1356.0	1357.0	1358.0	1359.0	1360.0	
105	Y5	0	190	610	1400	2480	3820	5370	7170	9040	
106	Y5	0	190	305	445	610	810	1040	1300	1600	
107	Y5	1346.5	1352	1353	1354	1355	1356	1357	1358	1359	
108	Y5	1352.0								1360	
109	Y5	1353.0									
110	K	99									

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT	1
ROUTE HYDROGRAPH TO	1
ROUTE HYDROGRAPH TO	2
ROUTE HYDROGRAPH TO	3
ROUTE HYDROGRAPH TO	4
ROUTE HYDROGRAPH TO	5
RUNOFF HYDROGRAPH AT	6
ROUTE HYDROGRAPH TO	6
ROUTE HYDROGRAPH TO	7
ROUTE HYDROGRAPH TO	8
ROUTE HYDROGRAPH TO	9
RUNOFF HYDROGRAPH AT	10
COMBINE 3 HYDROGRAPHS AT	11
ROUTE HYDROGRAPH TO	12
END OF NETWORK	

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 01 APR 80

RUN DATE: 81/03/04.
TIME: 04.28.54.

LAKE QUINN

OVERTOPPING ANALYSIS
page 2/12

LAKE GUINN DAM DER NO. 90-64-43
DAM SAFETY INSPECTION PROGRAM 12-9-80
OVERTOPPING ANALYSIS *** PRELIMINARY ***

JOB SPECIFICATION
NO NHR NMIN IDAY IHR ININ METRO IPLT IPRT NSTAN
144 0 20 0 0 0 0 0 -3 0
JOPER 5 NWT LROPT TRACE
0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 6 LRTIO= 1
RTIOS= .01 .10 .20 .30 .50 1.00

SUB-AREA RUNOFF COMPUTATION

RUNOFF FROM DRAINAGE AREA ABOVE ROBINSON DAM

ISTAR ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
1 0 0 0 0 0 1 0 0

HYDROGRAPH DATA
IHYDG IUNG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
1 1 .50 0.00 9.74 0.00 0.000 0 1 0

PRECIP DATA
SPFE PMS RA R12 R24 R48 R72 R96
0.00 21.50 111.00 123.00 133.00 142.00 0.00 0.00
TRSPC COMPUTED BY THE PROGRAM IS .800

LOSS DATA
LROPT STRKR DLTR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSHY RTIMP
0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .05 0.00 0.00

UNIT HYDROGRAPH DATA
TP= 1.02 CP= .45 NTA= 0

RECESSION DATA
STRIO= -1.50 BRCSN= -.05 RTIOR= 2.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 3.33 AND R= 4.74 INTERVALS

UNIT HYDROGRAPH 27 END-OF-PERIOD ORDINATES, LAG= 1.03 HOURS, CP= .45 VOL= 1.00
21. 76. 128. 137. 115. 93. 75. 61. 49. 40.
32. 26. 21. 17. 14. 11. 9. 7. 6. 5.
4. 3. 2. 2. 1. 1.

HYDROGRAPH ROUTING

ROUTING ZONE'S THRU ROBINSON DAM AND SPILLWAY

ISTAR ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO
1 1 0 0 0 0 1 0 0
ROUTING DATA
GLOSS GLOSS AVG IRES ISAME IOPT IPMP LSTR
0.0 0.000 0.00 1 1 0 0
NSTPS NSTOL LAG ANSKK Y TSK STORA ISPRAT
1 0 0 0.000 0.000 0.000 -1643. -1

STAGE	1643.00	1643.50	1644.20	1644.50	1645.00	1646.00	1650.00	1655.00	
FLOW	0.00	12.00	45.00	90.00	390.00	1570.00	12030.00	37000.00	
CAPACITY=	0.	150.	190.	410.	660.	960.			
ELEVATION=	1628.	1643.	1644.	1650.	1655.	1660.			
CREL	1643.0	SPWID	0.0	CODW	0.0	FYPW	0.0	FLEV	0.0
						CODL	0.0	CAREA	0.0
								EXPL	0.0

LAKE GUINN

OVERTOPPING ANALYSIS

page 3/12

D-19

HYDROGRAPH ROUTING

DOWNSTREAM Y-SECTION 230 FEET FROM DAM (ROBINSON)

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2	1	0	0	0	0	1	0	0
ROUTING DATA								
CLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

DN(1)	DN(2)	DN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1622.0	1638.0	230.	.00900

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

100.00	1638.00	142.00	1630.00	162.00	1625.00	175.00	1622.00	190.00	1622.00
197.00	1625.00	207.00	1630.00	225.00	1638.00				

STORAGE	0.00	.08	.18	.31	.47	.64	.84	1.06	1.31	1.57
	1.86	2.18	2.53	2.90	3.30	3.73	4.19	4.67	5.19	5.72
OUTFLOW	0.00	33.99	116.74	248.65	451.16	736.24	1085.63	1501.21	1985.00	2539.10
	3162.58	3860.47	4640.03	5504.64	6457.67	7502.42	8642.14	9880.03	11219.25	12660.89
STAGE	1622.00	1622.84	1623.68	1624.53	1625.37	1626.21	1627.05	1627.89	1628.74	1629.58
	1630.42	1631.26	1632.11	1632.95	1633.79	1634.63	1635.47	1636.32	1637.16	1638.00
FLOW	0.00	33.99	116.74	248.65	451.16	736.24	1085.63	1501.21	1985.00	2539.10
	3162.58	3860.47	4640.03	5504.64	6457.67	7502.42	8642.14	9880.03	11219.25	12660.89

HYDROGRAPH ROUTING

ROUTE THRU THE 2ND DOWNSTREAM CROSS SECTION (ROBINSON)

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
3	1	0	0	0	0	1	0	0
ROUTING DATA								
CLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

DN(1)	DN(2)	DN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1620.0	1638.0	270.	.00900

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

100.00	1638.00	140.00	1627.80	180.00	1627.00	192.00	1620.00	202.00	1620.00
210.00	1627.00	277.00	1633.60	323.00	1638.00				

STORAGE	0.00	.07	.15	.25	.36	.49	.64	.80	1.04	1.51
	2.07	2.70	3.42	4.21	5.08	6.03	7.06	8.17	9.36	10.62
OUTFLOW	0.00	26.37	87.08	179.47	304.94	465.64	663.98	902.42	1232.01	1730.43
	2389.97	3207.67	4189.78	5344.29	6679.83	8203.65	9926.18	11857.69	14007.32	16384.06
STAGE	1620.00	1620.95	1621.89	1622.84	1623.79	1624.74	1625.69	1626.63	1627.58	1628.52
	1629.47	1630.42	1631.37	1632.32	1633.26	1634.21	1635.16	1636.11	1637.05	1638.00
FLOW	0.00	26.37	87.08	179.47	304.94	465.64	663.98	902.42	1232.01	1730.43
	2389.97	3207.67	4189.78	5344.29	6679.83	8203.65	9926.18	11857.69	14007.32	16384.06

LAKE QUINN

OVERTOPPING ANALYSIS

page 4/12

HYDROGRAPH ROUTING

ROUTE FLOW THRU 3RD DOWNSTREAM CROSS SECTION (ROBINSON)

ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
4	1	0	0	0	0	1	0	0
ROUTING DATA								
GLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS	NSTDL	LAG	AMSK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1400.0	1414.0	8200.	.02700

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

	100.00	1414.00	120.00	1406.00	170.00	1403.00	175.00	1400.00	178.00	1400.00
STORAGE	0.00	.57	1.46	2.66	4.17	6.66	10.99	17.31	29.68	47.28
	65.52	84.33	103.69	123.62	144.10	165.16	186.77	208.94	231.68	254.98
OUTFLOW	0.00	9.81	35.97	81.21	148.82	257.39	424.36	676.95	1096.65	1828.20
	2801.85	3982.01	5355.41	6913.70	8651.27	10564.28	12650.10	14906.96	17333.74	19929.80
STAGE	1400.00	1400.74	1401.47	1402.21	1402.95	1403.68	1404.42	1405.16	1405.89	1406.63
	1407.37	1408.11	1408.84	1409.58	1410.32	1411.05	1411.79	1412.53	1413.26	1414.00
FLOW	0.00	9.81	35.97	81.21	148.82	257.39	424.36	676.95	1096.65	1828.20
	2801.85	3982.01	5355.41	6913.70	8651.27	10564.28	12650.10	14906.96	17333.74	19929.80

HYDROGRAPH ROUTING

ROUTE FLOWS TO HEAD OF LAKE QUINN (FROM ROBINSON)

ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
5	1	0	0	0	0	1	0	0
ROUTING DATA								
GLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS	NSTDL	LAG	AMSK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1352.0	1380.0	4400.	.01090

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

	100.00	1380.00	500.00	1360.00	700.00	1353.00	705.00	1352.00	905.00	1352.00
STORAGE	0.00	31.55	75.42	134.65	209.24	299.18	403.04	514.29	632.12	756.54
	887.53	1025.11	1169.26	1320.00	1477.32	1641.22	1811.70	1988.76	2172.40	2362.63
OUTFLOW	0.00	1219.40	4192.66	9007.88	15858.67	24945.63	36846.88	51453.36	68427.94	87767.64
	109486.02	133607.09	160161.79	189185.89	220718.61	254801.62	291478.46	330793.92	372793.84	417524.75
STAGE	1352.00	1353.47	1354.95	1356.42	1357.89	1359.37	1360.84	1362.32	1363.79	1365.26
	1366.74	1368.21	1369.68	1371.16	1372.63	1374.11	1375.58	1377.05	1378.53	1380.00
FLOW	0.00	1219.40	4192.66	9007.88	15858.67	24945.63	36846.88	51453.36	68427.94	87767.64
	109486.02	133607.09	160161.79	189185.89	220718.61	254801.62	291478.46	330793.92	372793.84	417524.75

LAKE QUINN

OVERTOPPING ANALYSIS

Page 5/12

SUB-AREA RUNOFF COMPUTATION

RUNOFF FROM DRAINAGE AREA ABOVE BRONSONS POND

ISTAG 6 ICOMP 0 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 ISTAGE 0 IAUTO 0

HYDROGRAPH DATA
IHYDG 1 IUNG 1 TAREA 2.38 SNAP 0.00 TRSDA 9.74 TRSPY 0.00 RATIO 0.000 ISNOW 0 ISAME 1 LOCAL 0

PRECIP DATA
SPEE 0.00 PMS 21.50 R6 111.00 R12 123.00 R24 133.00 R48 142.00 R72 0.00 R96 0.00

TRSPY COMPUTED BY THE PROGRAM IS .800

LOSS DATA
LROPT 0 STRKR 0.00 DLTGR 0.00 RTIOL 1.00 ERAIN 0.00 STRKS 0.00 RTIOK 1.00 STRTL 1.00 CNSTL .05 ALSMX 0.00 RTIMP 0.00

UNIT HYDROGRAPH DATA
TP= 1.85 CP= .45 NTA= 0

RECESSION DATA
STRTO= -1.50 GRCSN= -.05 RTIOR= 2.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 5.85 AND R= 8.91 INTERVALS

UNIT HYDROGRAPH 51 END-OF-PERIOD ORDINATES, LAG= 1.86 HOURS, CP= .45 VOL= 1.00

24.	91.	184.	278.	347.	372.	352.	314.	281.	251.
224.	200.	179.	160.	143.	128.	114.	102.	91.	82.
73.	65.	58.	52.	47.	42.	37.	33.	30.	27.
24.	21.	19.	17.	15.	14.	12.	11.	10.	9.
8.	7.	6.	6.	5.	4.	4.	4.	3.	3.
3.									

HYDROGRAPH ROUTING

ROUTING XPMF'S THRU BRONSONS POND

ISTAG 6 ICOMP 1 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 ISTAGE 0 IAUTO 0

ROUTING DATA
GLOSS 0.0 CLOSS 0.000 AVG 0.00 IRES 1 ISAME 1 IOPT 0 IPMP 0 LSTR 0

NSTPS 1 NSTDL 0 LAG 0 AMSKY 0.000 X 0.000 TSK 0.000 STORA -1403. ISPRAT -1

STAGE	1403.10	1403.20	1403.60	1404.00	1405.00	1410.00	1415.00	1420.00
FLOW	0.00	.50	23.00	95.00	520.00	5310.00	13300.00	23500.00
CAPACITY=	0.	380.	385.	500.	890.	1490.	2320.	
ELEVATION=	1382.	1403.	1403.	1405.	1410.	1415.	1420.	

CREL 1403.0 SPWID 0.0 COWW 0.0 EXPW 0.0 ELEV 0.0 COWL 0.0 CAREA 0.0 EXPL 0.0

DAM DATA
TOPEL 1403.1 COOD 0.0 EXPD 0.0 DAMWID 0.

LAKE GUNW

OVERTOPPING ANALYSIS

6/12

HYDROGRAPH ROUTING

ROUTE FLOWS THRU 1ST DOWNSTREAM CROSS SECTION (BRONSON)

ISTAO	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IALTO
7	1	0	0	0	0	1	0	0
ROUTING DATA								
CLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1393.0	1411.0	200.	.00800

CROSS SECTION COORDINATES—STA.ELEV.STA.ELEV—ETC

100.00	1411.00	125.00	1405.00	136.00	1397.00	140.00	1393.00	190.00	1393.00
186.00	1397.00	190.00	1402.00	230.00	1411.00				

STORAGE	0.00	.18	.37	.57	.78	1.00	1.23	1.47	1.71	1.97
	2.23	2.52	2.84	3.17	3.54	3.95	4.39	4.87	5.38	5.92
OUTFLOW	0.00	97.40	309.72	610.77	991.07	1481.42	2062.78	2723.72	3462.41	4277.45
	5165.41	6134.72	7191.79	8333.24	9565.29	10908.94	12368.85	13950.25	15658.52	17496.99
STAGE	1393.00	1393.95	1394.89	1395.84	1396.79	1397.74	1398.68	1399.63	1400.58	1401.52
	1402.47	1403.42	1404.37	1405.32	1406.26	1407.21	1408.16	1409.11	1410.05	1411.00
FLOW	0.00	97.40	309.72	610.77	991.07	1481.42	2062.78	2723.72	3462.41	4277.45
	5165.41	6134.72	7191.79	8333.24	9565.29	10908.94	12368.85	13950.25	15658.52	17496.99

HYDROGRAPH ROUTING

ROUTE FLOWS THRU 2ND DOWNSTREAM CROSS SECTION (BRONSON)

ISTAO	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IALTO
8	1	0	0	0	0	1	0	0
ROUTING DATA								
CLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1368.0	1400.0	3100.	.00800

CROSS SECTION COORDINATES—STA.ELEV.STA.ELEV—ETC

100.00	1400.00	200.00	1380.00	250.00	1373.00	255.00	1368.00	285.00	1368.00
290.00	1372.00	350.00	1380.00	500.00	1400.00				

STORAGE	0.00	3.82	8.10	13.08	20.34	30.56	43.74	59.87	78.79	100.24
	124.21	150.71	179.72	211.27	245.33	281.92	321.03	362.67	406.82	453.51
OUTFLOW	0.00	190.22	607.59	1237.68	2179.92	3481.38	5215.69	7446.81	10258.71	13661.16
	17688.99	22381.18	27775.99	33910.87	40822.44	48546.65	57118.60	66572.79	76943.05	88262.64
STAGE	1368.00	1369.68	1371.37	1373.05	1374.74	1376.42	1378.11	1379.79	1381.47	1383.16
	1384.34	1386.53	1388.71	1389.89	1391.58	1393.26	1394.95	1396.63	1398.32	1400.00
FLOW	0.00	190.22	607.59	1237.68	2179.92	3481.38	5215.69	7446.81	10258.71	13661.16
	17688.99	22381.18	27775.99	33910.87	40822.44	48546.65	57118.60	66572.79	76943.05	88262.64

LAKE QUINN

OVERTOPPING ANALYSIS

page 1/12

HYDROGRAPH ROUTING

ROUTE FLOWS TO HEAD OF LAKE QUINN (FROM BRUNSON)

ISTAD	ICOMP	IECON	ITAPE	IPLT	IPRT	INAME	ISTAGE	IAUTO
0	1	0	0	0	0	1	0	0
ROUTING DATA								
CLOSS	CLOSS	AVG	IRES	ISAME	IOPF	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTEP								
1	0	LAG	AMSK	X	TSY	STORA	ISPRAT	
		0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1357.0	1375.0	1000.	.01100

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC

100.00	1375.00	106.00	1369.00	240.00	1362.00	280.00	1357.00	320.00	1357.00
323.00	1359.00	340.00	1369.00	356.00	1375.00				

STAGE	0.00	2.97	2.13	3.40	5.05	6.81	8.82	11.27	14.15	17.45
	21.17	25.23	28.92	34.92	40.07	45.30	50.60	55.98	61.44	66.97
OUTFLOW	0.00	119.62	392.95	820.53	1396.78	2128.59	3132.45	4381.98	5864.00	7599.11
	9605.97	11902.10	14504.26	17490.76	20926.56	24673.53	28720.66	33059.28	37682.40	42584.24
STAGE	1357.00	1357.95	1358.89	1359.84	1360.79	1361.74	1362.68	1363.63	1364.58	1365.52
	1365.47	1367.42	1369.37	1369.30	1370.26	1371.21	1372.16	1373.11	1374.05	1375.00
FLOW	0.00	119.62	392.95	820.53	1396.78	2128.59	3132.45	4381.98	5864.00	7599.11
	9605.97	11902.10	14504.26	17490.76	20926.56	24673.53	28720.66	33059.28	37682.40	42584.24

SUB-AREA RUNOFF COMPUTATION

RUNOFF FROM UNCONTROLLED DRAINAGE AREA ABOVE LAKE QUINN

ISTAD	ICOMP	IECON	ITAPE	IPLT	IPRT	INAME	ISTAGE	IAUTO
10	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYD	IIMG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	6.86	0.00	9.74	0.00	0.000	0	1	0

PRECIP DATA

SPFE	PMF	RA	R12	R24	R48	R72	R96
0.00	21.50	111.00	129.00	133.00	142.00	0.00	0.00

TR-FC COMPUTED BY THE PROGRAM IS .200

LOSS DATA

LRPT	STKE	ILTR	RTOL	FRAN	STKE	RTOL	STRT	DNST	ALSMY	RTIME
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 2.35 CP= .45 NTA= 0

RECESSION DATA

STRIC= -1.50 GRON= -.05 RTIOR= 2.00

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 7.53 AND R=11.00 INTERVALS

UNIT HYDROGRAPH 63 END-OF-PERIOD ORDINATES. LAG= 2.36 HOURS. CP= .45. VQ= 1.00

40.	148.	301.	478.	649.	780.	854.	856.	797.	720.
444.	607.	554.	506.	462.	422.	385.	351.	321.	290.
268.	244.	222.	204.	186.	170.	155.	142.	129.	118.
108.	98.	90.	82.	75.	68.	62.	57.	52.	48.
43.	40.	36.	32.	30.	28.	26.	23.	21.	19.
17.	16.	15.	13.	12.	11.	10.	9.	8.	7.
7.	6.	6.							

LAKE QUINN

OPERATING ANALYSIS
PAGE 8/12

COMBINE HYDROGRAPHS

COMBINE 3 HYDROGRAPHS AT LAKE QUINN ROUTE COMBINED HYD. THRU LAKE

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
11	3	0	0	0	0	1	0	0

HYDROGRAPH ROUTING

ROUTING %PME'S THRU LAKE QUINN

	ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO	
	12	1	0	0	0	0	1	0	0	
ROUTING DATA										
	GLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR		
	0.0	0.000	0.00	1	1	0	0	0		
	NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT		
	1	0	0	0.000	0.000	0.000	-1352.	-1		
STAGE	1352.00	1353.00	1354.00	1355.00	1356.00	1357.00	1358.00	1359.00	1360.00	1370.00
FLOW	0.00	190.00	610.00	1400.00	2480.00	3820.00	5370.00	7170.00	9040.00	36000.00
CAPACITY=	0.	190.	305.	445.	610.	810.	1040.	1300.	1600.	1930.
ELEVATION=	1347.	1352.	1353.	1354.	1355.	1356.	1357.	1358.	1359.	1360.

CREL	SPWID	COOW	EXPW	ELEV	COOL	CAREA	EXPL
1352.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM

TOPEL	COOD	DAMWID
1353.0	0	0.

STATION 12. PLAN 1. RATIO 1

1

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS					
				RATIO 1 .01	RATIO 2 .10	RATIO 3 .20	RATIO 4 .30	RATIO 5 .50	RATIO 6 1.00
HYDROGRAPH AT	1	.50	1	14.	138.	276.	414.	690.	1380.
	(1.29)	(.39)	3.91)	7.81)	11.72)	19.54)	39.07)
ROUTED TO	1	.50	1	3.	42.	188.	332.	638.	1303.
	(1.29)	(.08)	1.20)	5.32)	9.41)	18.06)	36.88)
ROUTED TO	2	.50	1	3.	42.	188.	333.	638.	1302.
	(1.29)	(.08)	1.20)	5.34)	9.43)	18.08)	36.86)
ROUTED TO	3	.50	1	3.	42.	188.	333.	639.	1301.
	(1.29)	(.08)	1.20)	5.33)	9.44)	18.09)	36.83)
ROUTED TO	4	.50	1	3.	42.	185.	326.	617.	1267.
	(1.29)	(.08)	1.19)	5.23)	9.23)	17.48)	35.87)
ROUTED TO	5	.50	1	3.	42.	180.	320.	603.	1241.
	(1.29)	(.08)	1.19)	5.11)	9.07)	17.09)	35.14)
HYDROGRAPH AT	6	2.38	1	44.	442.	884.	1326.	2210.	4420.
	(6.16)	(1.25)	12.51)	25.03)	37.54)	62.57)	125.15)
ROUTED TO	6	2.38	1	11.	358.	781.	1198.	2008.	4019.
	(6.16)	(.32)	10.13)	22.12)	33.92)	56.85)	113.79)
ROUTED TO	7	2.38	1	11.	358.	780.	1198.	2008.	4018.
	(6.16)	(.32)	10.13)	22.09)	33.92)	56.87)	113.78)
ROUTED TO	8	2.38	1	11.	358.	781.	1196.	2007.	4017.
	(6.16)	(.32)	10.13)	22.10)	33.88)	56.82)	113.75)
ROUTED TO	9	2.38	1	11.	358.	781.	1196.	2006.	4017.
	(6.16)	(.32)	10.13)	22.12)	33.87)	56.81)	113.74)
HYDROGRAPH AT	10	6.86	1	114.	1137.	2273.	3410.	5683.	11366.
	(17.77)	(3.22)	32.19)	64.37)	96.56)	160.93)	321.85)
3 COMBINED	11	9.74	1	119.	1485.	3162.	4872.	8206.	16439.
	(25.23)	(3.37)	42.04)	89.54)	137.96)	232.36)	465.49)
ROUTED TO	12	9.74	1	63.	1094.	2484.	3903.	6669.	14064.
	(25.23)	(1.79)	30.98)	70.33)	110.53)	188.86)	398.24)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	1643.00	1643.00	1644.20
STORAGE	150.	150.	190.
OUTFLOW	0.	0.	45.

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.01	1643.12	0.00	154.	3.	0.00	44.67	0.00
.10	1644.14	0.00	188.	42.	0.00	44.00	0.00
.20	1644.64	.44	208.	188.	7.67	42.33	0.00
.30	1644.90	.70	217.	332.	8.67	41.67	0.00
.50	1645.21	1.01	228.	638.	9.67	41.00	0.00
1.00	1645.77	1.57	250.	1303.	11.33	41.00	0.00

ROBINSO
T-500
LAW

PLAN 1 STATION 2

RATIO	MAXIMUM FLOW CFS	MAXIMUM STAGE FT	TIME HOURS
.01	3.	1622.1	44.67
.10	42.	1622.9	44.00
.20	188.	1624.1	42.33
.30	332.	1624.9	41.67
.50	638.	1625.9	41.00
1.00	1302.	1627.5	41.00

PLAN 1 STATION 3

RATIO	MAXIMUM FLOW CFS	MAXIMUM STAGE FT	TIME HOURS
.01	3.	1620.1	44.67
.10	42.	1621.2	44.00
.20	188.	1622.9	42.33
.30	332.	1624.0	41.67
.50	639.	1625.6	41.00
1.00	1301.	1627.7	41.00

PLAN 1 STATION 4

RATIO	MAXIMUM FLOW CFS	MAXIMUM STAGE FT	TIME HOURS
.01	3.	1400.2	45.33
.10	42.	1401.6	44.33
.20	185.	1403.2	42.67
.30	326.	1404.0	42.00
.50	617.	1405.0	41.67
1.00	1267.	1406.1	41.33

PLAN 1 STATION 5

RATIO	MAXIMUM FLOW CFS	MAXIMUM STAGE FT	TIME HOURS
.01	3.	1352.0	46.00
.10	42.	1352.1	44.67
.20	180.	1352.2	43.00
.30	320.	1352.4	42.67
.50	603.	1352.7	42.00
1.00	1241.	1353.5	41.67

SUMMARY OF DAM SAFETY ANALYSIS

ARE QUINN

OVERTOPPING ANALYSIS
page 11/12

PLAN 1

.....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1403.00 380. 0.	SPILLWAY CREST 1403.00 380. 0.	TOP OF DAM 1403.10 385. 0.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.01	1403.39	.29	403.	11.	12.00	47.33	0.00
.10	1404.62	1.52	477.	358.	31.33	43.33	0.00
.20	1405.27	2.17	521.	781.	32.33	42.67	0.00
.30	1405.71	2.61	555.	1198.	32.67	42.67	0.00
.50	1406.55	3.45	621.	2008.	33.00	42.67	0.00
1.00	1408.65	5.55	785.	4019.	33.33	42.67	0.00

ERANDSON
FORD
DAM

PLAN 1 STATION 7

RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS
.01	11.	1393.1	47.33
.10	358.	1395.0	43.33
.20	780.	1396.3	42.67
.30	1198.	1397.2	42.67
.50	2008.	1398.6	42.67
1.00	4018.	1401.2	42.67

PLAN 1 STATION 8

RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS
.01	11.	1368.1	47.67
.10	358.	1370.4	43.33
.20	781.	1371.8	43.00
.30	1196.	1372.9	42.67
.50	2007.	1374.4	42.67
1.00	4017.	1376.9	42.67

PLAN 1 STATION 9

RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS
.01	11.	1357.1	47.67
.10	358.	1358.8	43.33
.20	781.	1359.8	43.00
.30	1196.	1360.5	42.67
.50	2006.	1361.6	42.67
1.00	4017.	1363.4	42.67

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

.....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1352.00 190. 0.	SPILLWAY CREST 1352.00 190. 0.	TOP OF DAM 1353.00 305. 190.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.01	1352.33	0.00	228.	63.	0.00	46.33	0.00
.10	1354.61	1.61	546.	1094.	8.67	44.67	0.00
.20	1356.00	3.00	811.	2484.	12.67	44.33	0.00
.30	1357.05	4.05	1054.	3903.	23.33	44.00	0.00
.50	1358.72	5.72	1517.	6669.	30.00	44.00	0.00
1.00	1361.86	8.86	2545.	14064.	31.33	43.67	0.00

LAKE
QUINN
DAM

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 01 APR 80

D-28

LAKE QUINN
INTERPRETING ANALYSIS
page 12/12

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 01 APR 80

1	A1	LAKE QUINN DAM DER NO. 90-64-43									
2	A2	DAM SAFETY INSPECTION PROGRAM 12-19-80									
3	A3	BREACHING ANALYSIS *** PRELIMINARY ***									
4	R	144	0	20	0	0	0	0	0	-3	0
5	B1	5	0	0	0	0	0	0	0	0	0
6	J1	4	1	1							
7	K1	0.10									
8	K	0	1	0	0	0	0	1	0	0	0
9	K1	RUNOFF FROM DRAINAGE AREA ABOVE ROBINSON DAM									
10	M	1	1	0.50	0	9.74	0	0	0	1	0
11	P	0	21.5	111	123	133	142				
12	T	0	0	0	0	0	0	1.0	0.05	0	0
13	W	1.02	0.45								
14	X	-1.5	-0.05	2							
15	K	1	1	0	0	0	0	1	0	0	0
16	K1	ROUTING XPM'S THRU ROBINSON DAM AND SPILLWAY									
17	Y	0	0	0	1	0	0	0	0	0	0
18	Y1	1	0	0	0	0	0	-1643	-1	0	0
19	Y4	1643.0	1643.5	1644.2	1644.5	1645.0	1646.0	1650.0	1655.0		
20	Y5	0	12.0	45.0	90.0	390.0	1570.0	12030.0	37000.0		
21	SS	0	150	190	410	660	960				
22	SE1	27.7	1643.0	1644.2	1650.0	1655.0	1660.0				
23	SS1	1643.0									
24	SD1	1644.2									
25	K	1	2	0	0	0	0	1	0	0	0
26	K1	DOWNSTREAM X-SECTION 230 FEET FROM DAM (ROBINSON)									
27	Y	0	0	0	1	1	0	0	0	0	0
28	Y1	1	0	0	0	0	0	0	0	0	0
29	Y6	0.07	0.05	0.07	1622	1638	230	0.0090	0	0	0
30	Y7	100	1638	142	1630	162	1625	175	1622	190	1622
31	Y7	197	1625	207	1630	225	1638				
32	K	1	3	0	0	0	0	1	0	0	0
33	K1	ROUTE THRU THE 2ND DOWNSTREAM CROSS SECTION (ROBINSON)									
34	Y	0	0	0	1	1	0	0	0	0	0
35	Y1	1	0	0	0	0	0	0	0	0	0
36	Y6	0.07	0.05	0.07	1620	1638	270	0.0090	0	0	0
37	Y7	100	1638	140	1627.8	180	1627	192	1620	202	1620
38	Y7	210	1627	277	1633.6	323	1638				
39	K	1	4	0	0	0	0	1	0	0	0
40	K1	ROUTE FLOW THRU 3RD DOWNSTREAM CROSS SECTION (ROBINSON)									
41	Y	0	0	0	1	1	0	0	0	0	0
42	Y1	1	0	0	0	0	0	0	0	0	0
43	Y6	0.07	0.05	0.07	1400	1414	8200	0.027	0	0	0
44	Y7	100	1414	120	1406	170	1403	175	1400	178	1400
45	Y7	185	1405	246	1406	270	1414				
46	K	1	5	0	0	0	0	1	0	0	0
47	K1	ROUTE FLOWS TO HEAD OF LAKE QUINN (FROM ROBINSON)									
48	Y	0	0	0	1	1	0	0	0	0	0
49	Y1	1	0	0	0	0	0	0	0	0	0
50	Y6	0.07	0.05	0.07	1352	1380	4400	0.0109	0	0	0
51	Y7	100	1380	500	1360	700	1353	705	1352	905	1352
52	Y7	910	1353	1200	1360	1400	1380				
53	K	0	6	0	0	0	0	1	0	0	0
54	K1	RUNOFF FROM DRAINAGE AREA ABOVE BRONSONS POND									
55	M	1	1	2.38	0	9.74	0	0	0	1	0
56	P	0	21.5	111	123	133	142				
57	T	0	0	0	0	0	0	1.0	0.05	0	0
58	W	1.05	0.45								
59	X	-1.5	-0.05	2							
60	K	1	6	0	0	0	0	1	0	0	0
61	K1	ROUTING XPM'S THRU BRONSONS POND									
62	Y	0	0	0	1	1	0	0	0	0	0
63	Y1	1	0	0	0	0	0	-1403	-1	0	0
64	Y4	1403.1	1403.2	1403.6	1404.0	1405.0	1410.0	1415.0	1420.0		
65	Y5	0	0.5	23.0	95.0	520.0	5210.0	13300.0	23500.0		
66	SS	0	200	285	500	890	1490				
67	SE1	250.0	1403.6	1403.1	1405.0	1410.0	1415.0	1420.0			
68	SS1	1403.1									
69	SD1	1403.6									

LAKE QUINN
 BREACH ANALYSIS
 PAGE 1/10

70	K	1	7	0	0	0	0	1				
71	K1	ROUTE FLOWS THRU 1ST DOWNSTREAM CROSS SECTION (BRONSON)										
72	Y	0	0	0	1	1	0	0				
73	Y1	1	0	0	0	0	0	0				
74	Y6	0.07	0.05	0.07	1393	1411	200	0.008				
75	Y7	100	1411	125	1405	136	1397	140	1393	180	1393	
76	Y7	186	1397	190	1402	230	1411					
77	K	1	8	0	0	0	0	1				
78	K1	ROUTE FLOWS THRU 2ND DOWNSTREAM CROSS SECTION (BRONSON)										
79	Y	0	0	0	1	1	0	0				
80	Y1	1	0	0	0	0	0	0				
81	Y6	0.07	0.05	0.07	1368	1400	3100	0.008				
82	Y7	100	1400	200	1380	250	1373	255	1368	285	1368	
83	Y7	290	1372	350	1380	500	1400					
84	K	1	9	0	0	0	0	1				
85	K1	ROUTE FLOWS TO HEAD OF LAKE GUINN (FROM BRONSON)										
86	Y	0	0	0	1	1	0	0				
87	Y1	1	0	0	0	0	0	0				
88	Y6	0.07	0.05	0.07	1357	1375	1000	0.011				
89	Y7	100	1375	106	1369	240	1362	280	1357	320	1357	
90	Y7	323	1359	340	1369	356	1375					
91	K	0	10	0	0	0	0	1	0	0	0	
92	K1	RUNOFF FROM UNCONTROLLED DRAINAGE AREA ABOVE LAKE GUINN										
93	M	1	1	6.86	0	9.74	0	0	0	1	0	
94	P	0	21.5	121	123	133	142					
95	T	0	0	0	0	0	0	1.0	0.05	0	0	
96	W	2.35	0.45									
97	X	-1.5	-0.05	2								
98	K	3	11	0	0	0	0	1				
99	K1	COMBINE 3 HYDROGRAPHS AT LAKE GUINN ROUTE COMBINED HYD. THRU LAKE										
100	K	1	12	0	0	0	0	1	0	0	0	
101	K1	ROUTING XPH'S THRU LAKE GUINN										
102	Y	0	0	0	1	1	0	0	0	0	0	
103	Y1	1	0	0	0	0	0	-1352	-1	0	0	
104	Y4	1352.0	1353.0	1354.0	1355.0	1356.0	1357.0	1358.0	1359.0	1360.0	1370.0	
105	Y5	0	190	610	1400	2480	2820	5370	7170	9040	36000	
106	Y6	0	190	305	445	610	810	1040	1300	1600	1930	
107	SE	1343.9	1352	1353	1354	1355	1356	1357	1358	1359	1360	
108	SE	1352.0										
109	SE	1353.0										
110	SB	66	0.5	1344	0.33	1353	1400					
111	SB	66	0.5	1344	0.33	1353	1354.5					
112	SB	66	0.5	1344	1.00	1353	1354.5					
113	SB	66	0.5	1344	2.00	1353	1354.5					
114	K	1	13	0	0	0	0	1				
115	K1	ROUTE FLOWS THRU 1ST DOWNSTREAM CROSS SECTION (GUINN)										
116	Y	0	0	0	1	1	0	0				
117	Y1	1	0	0	0	0	0	0				
118	Y6	0.07	0.05	0.07	1340	1358	100	0.01				
119	Y7	100	1358	115	1344	157	1343	163	1340	253	1340	
120	Y7	265	1344	286	1351	308	1358					
121	K	1	14	0	0	0	0	1				
122	K1	ROUTE FLOWS THRU 2ND DOWNSTREAM CROSS SECTION (GUINN)										
123	Y	0	0	0	1	1	0	0				
124	Y1	1	0	0	0	0	0	0				
125	Y6	0.07	0.05	0.07	1319	1339	3900	0.0054				
126	Y7	100	1339	168	1332	193	1329	218	1319	258	1319	
127	Y7	268	1329	278	1338	282	1339					
128	K	1	15	0	0	0	0	1				
129	K1	ROUTE FLOWS THRU 3RD CROSS SECTION (GUINN)										
130	Y	0	0	0	1	1	0	0				
131	Y1	1	0	0	0	0	0	0				
132	Y6	0.07	0.05	0.07	1230	1245	10500	0.0085				
133	Y7	100	1245	150	1239	202	1236	205	1230	245	1230	
134	Y7	248	1235	282	1238.4	325	1245					
135	K	99										

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

LAKE GUINN
BREACH ANALYSIS
page 2/10

```

RUNOFF HYDROGRAPH AT      1
ROUTE HYDROGRAPH TO      1
ROUTE HYDROGRAPH TO      2
ROUTE HYDROGRAPH TO      3
ROUTE HYDROGRAPH TO      4
ROUTE HYDROGRAPH TO      5
ROUTE HYDROGRAPH AT      6
ROUTE HYDROGRAPH TO      6
ROUTE HYDROGRAPH TO      7
ROUTE HYDROGRAPH TO      8
ROUTE HYDROGRAPH TO      9
ROUTE HYDROGRAPH AT     10
COMBINE 3 HYDROGRAPHS AT 11
ROUTE HYDROGRAPH TO     12
ROUTE HYDROGRAPH TO     13
ROUTE HYDROGRAPH TO     14
ROUTE HYDROGRAPH TO     15
END OF NETWORK

```

```

*****
FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 01 APR 80
*****

```

```

RUN DATE* 81/03/04.
TIME* 04.30.54.

```

```

LAKE QUINN DAM DER NO. 90-64-43
DAM SAFETY INSPECTION PROGRAM 12-19-80
BREACHING ANALYSIS *** PRELIMINARY ***

```

```

          JOB SPECIFICATION
NO      NHR      NMIN      IDAY      IHR      IMIN      METRC      IPLT      IPRT      NSTAN
144      0      20      0      0      0      0      0      -3      0
          JOPER      NWT      LROPT      TRACE
          5      0      0      0

```

```

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 4 NRTIO= 1 LRTIO= 1
RTIOS= .10

```

```

*****

```

DAM BREACH DATA

```

          DAM BREACH DATA
BRWID      Z      ELEM      TFALL      WSEL      FAILEL
66.      .50 1344.00      .33 1353.00 1400.00

```

DAM BREACH DATA

```

          DAM BREACH DATA
BRWID      Z      ELEM      TFALL      WSEL      FAILEL
66.      .50 1344.00      .33 1353.00 1354.50

```

STATION 12, PLAN 2, RATIO 1

```

          DAM BREACH DATA
BRWID      Z      ELEM      TFALL      WSEL      FAILEL
66.      .50 1344.00      1.00 1353.00 1354.50

```

STATION 12, PLAN 3, RATIO 1

```

          DAM BREACH DATA
BRWID      Z      ELEM      TFALL      WSEL      FAILEL
66.      .50 1344.00      2.00 1353.00 1354.50

```

STATION 12, PLAN 4, RATIO 1

LAKE QUINN
BREACH ANALYSIS
Page 3/10

HYDROGRAPH ROUTING

ROUTE FLOWS THRU 1ST DOWNSTREAM CROSS SECTION (QUINN)

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
13	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

CLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	0.	0

NORMA DEPTH CHANNEL ROUTING

DN(1)	DN(2)	DN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1340.0	1358.0	100.	.01000

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

100.00	1358.00	115.00	1344.00	157.00	1343.00	163.00	1340.00	253.00	1340.00
265.00	1344.00	286.00	1351.00	308.00	1358.00				

STORAGE	0.00	.20	.41	.63	.89	1.22	1.56	1.90	2.26	2.62
	2.99	3.37	3.76	4.15	4.56	4.97	5.39	5.82	6.26	6.71
SECTION	0.00	246.67	788.86	1562.97	2581.64	3942.97	5603.00	7523.76	9691.65	12097.29
	14733.78	17595.86	20678.93	23979.86	27497.20	31229.08	35174.10	39331.19	43699.55	48278.65
STAGE	1340.00	1340.95	1341.89	1342.84	1343.79	1344.74	1345.68	1346.63	1347.58	1348.53
	1349.47	1350.42	1351.37	1352.32	1353.26	1354.21	1355.16	1356.11	1357.05	1358.00
FLOW	0.00	246.67	788.86	1562.97	2581.64	3942.97	5603.00	7523.76	9691.65	12097.29
	14733.78	17595.86	20678.93	23979.86	27497.20	31229.08	35174.10	39331.19	43699.55	48278.65

HYDROGRAPH ROUTING

ROUTE FLOWS THRU 2ND DOWNSTREAM CROSS SECTION (QUINN)

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
14	1	0	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

CLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

NSTPS	NSTDL	LAG	AMSKY	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	0.	0

NORMA DEPTH CHANNEL ROUTING

DN(1)	DN(2)	DN(3)	ELNVT	ELMAX	RLNTH	SEL
.0700	.0500	.0700	1319.0	1339.0	3900.	.00540

CROSS SECTION COORDINATES--STA.ELEV.STA.ELEV--ETC

100.00	1339.00	168.00	1332.00	193.00	1329.00	218.00	1319.00	258.00	1319.00
268.00	1329.00	278.00	1338.00	282.00	1339.00				

STORAGE	0.00	3.94	8.22	12.87	17.86	23.19	28.87	34.90	41.27	47.99
	55.13	63.14	72.08	81.99	92.96	105.01	118.13	132.33	147.59	164.07
SECTION	0.00	96.05	307.92	612.59	1003.21	1477.28	2034.22	2674.55	3399.34	4210.12
	5192.03	6266.33	7661.17	9085.35	10650.38	12366.52	14242.22	16285.50	18504.02	20891.99
STAGE	1319.00	1320.05	1321.11	1322.16	1323.21	1324.26	1325.32	1326.37	1327.42	1328.47
	1329.53	1330.58	1331.63	1332.68	1333.74	1334.79	1335.84	1336.89	1337.95	1339.00
FLOW	0.00	96.05	307.92	612.59	1003.21	1477.28	2034.22	2674.55	3399.34	4210.12
	5192.03	6266.33	7661.17	9085.35	10650.38	12366.52	14242.22	16285.50	18504.02	20891.99

LAKE QUINN

BREACH ANALYSIS

Page 4/10

HYDROGRAPH ROUTING

ROUTE FLOWS THRU 3RD CROSS SECTION (QUINN)

ISTAG 15 ICOMP 1 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 ISTAGE 0 IALTO 0

ALL PLANS HAVE SAME ROUTING DATA

GLOSS 0.0 CLOSS 0.000 AVG 0.00 IRES 1 ISAME 1 IOPT 0 IPMP 0 LSTP 0
NSTPS 1 NSTDL 0 LAG 0 AMSKK 0.000 X 0.000 TSK 0.000 STORA 0. ISPRAT 0

NORMAL DEPTH CHANNEL ROUTING

QN(1) QN(2) QN(3) ELNVT ELMAX RLNTH SEL
.0700 .0500 .0700 1230.0 1245.0 10500. .00850

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC

100.00 1245.00 150.00 1239.00 202.00 1236.00 205.00 1230.00 245.00 1230.00
248.00 1235.00 282.00 1238.40 325.00 1245.00

STORAGE	0.00	7.69	15.55	23.58	31.77	40.13	48.65	57.65	68.35	82.70
	101.16	123.69	149.67	177.99	208.54	241.31	276.32	313.56	353.04	394.74
OUTFLOW	0.00	73.27	230.22	448.28	717.92	1033.32	1390.45	1800.49	2277.55	2844.98
	3514.16	4306.98	5249.17	6334.72	7559.33	8927.16	10442.82	12111.15	13937.07	15925.54
STAGE	1230.00	1230.79	1231.58	1232.37	1233.16	1233.95	1234.74	1235.53	1236.32	1237.11
	1237.89	1238.68	1239.47	1240.26	1241.05	1241.84	1242.63	1243.42	1244.21	1245.00
FLOW	0.00	73.27	230.22	448.28	717.92	1033.32	1390.45	1800.49	2277.55	2844.98
	3514.16	4306.98	5249.17	6334.72	7559.33	8927.16	10442.82	12111.15	13937.07	15925.54

1

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO	1
					.10
HYDROGRAPH AT	1	.50	1	138.	
	(1.29)	(3.91)	(
			2	138.	
			(3.91)	(
			3	138.	
			(3.91)	(
			4	138.	
			(3.91)	(
ROUTED TO	1	.50	1	42.	
	(1.29)	(1.20)	(
			2	42.	
			(1.20)	(
			3	42.	
			(1.20)	(
			4	42.	
			(1.20)	(

LAKE QUINN
BREACH ANALYSIS
Page 5/10

ROUTED TO	2	.50 (1.29)	1	42. (1.20)	ROUTED TO	9	2.38 (6.16)	1	358. (10.13)
			2	42. (1.20)				2	358. (10.13)
			3	42. (1.20)				3	358. (10.13)
			4	42. (1.20)				4	358. (10.13)
ROUTED TO	3	.50 (1.29)	1	42. (1.20)	HYDROGRAPH AT	10	6.86 (17.77)	1	1137. (32.19)
			2	42. (1.20)				2	1137. (32.19)
			3	42. (1.20)				3	1137. (32.19)
			4	42. (1.20)				4	1137. (32.19)
ROUTED TO	4	.50 (1.29)	1	42. (1.19)	3 COMBINED	11	9.74 (25.23)	1	1485. (42.04)
			2	42. (1.19)				2	1485. (42.04)
			3	42. (1.19)				3	1485. (42.04)
			4	42. (1.19)				4	1485. (42.04)
ROUTED TO	5	.50 (1.29)	1	42. (1.19)	ROUTED TO	12	9.74 (25.23)	1	1094. (30.99)
			2	42. (1.19)				2	7794. (220.71)
			3	42. (1.19)				3	6793. (192.35)
			4	42. (1.19)				4	5559. (157.42)
HYDROGRAPH AT	6	2.38 (6.16)	1	442. (12.51)	ROUTED TO	13	9.74 (25.23)	1	1095. (31.00)
			2	442. (12.51)				2	7690. (217.75)
			3	442. (12.51)				3	6770. (191.71)
			4	442. (12.51)				4	5553. (157.23)
ROUTED TO	6	2.38 (6.16)	1	358. (10.13)	ROUTED TO	14	9.74 (25.23)	1	1095. (30.99)
			2	358. (10.13)				2	7606. (215.38)
			3	358. (10.13)				3	6173. (174.80)
			4	358. (10.13)				4	5277. (149.44)
ROUTED TO	7	2.38 (6.16)	1	358. (10.13)	ROUTED TO	15	9.74 (25.23)	1	1090. (30.88)
			2	358. (10.13)				2	5860. (165.94)
			3	358. (10.13)				3	5216. (147.71)
			4	358. (10.13)				4	4604. (130.37)
ROUTED TO	8	2.38 (6.16)	1	358. (10.13)					
			2	358. (10.13)					
			3	358. (10.13)					
			4	358. (10.13)					

LAKE QUINN
PEACH ANALYSIS
page 6/10

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1643.00 150. 0.	SPILLWAY CREST 1643.00 150. 0.	TOP OF DAM 1644.20 190. 45.				
	RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.10	1644.14	0.00	188.	42.	0.00	44.00	0.00
PLAN 2	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1643.00 150. 0.	SPILLWAY CREST 1643.00 150. 0.	TOP OF DAM 1644.20 190. 45.				
	RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.10	1644.14	0.00	188.	42.	0.00	44.00	0.00
PLAN 3	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1643.00 150. 0.	SPILLWAY CREST 1643.00 150. 0.	TOP OF DAM 1644.20 190. 45.				
	RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.10	1644.14	0.00	188.	42.	0.00	44.00	0.00
PLAN 4	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1643.00 150. 0.	SPILLWAY CREST 1643.00 150. 0.	TOP OF DAM 1644.20 190. 45.				
	RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.10	1644.14	0.00	188.	42.	0.00	44.00	0.00
PLAN 1	STATION	2	PLAN 1	STATION	3			
RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	
.10	42.	1622.9	44.00	.10	42.	1621.2	44.00	
PLAN 2	STATION	2	PLAN 2	STATION	3			
RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	
.10	42.	1622.9	44.00	.10	42.	1621.2	44.00	
PLAN 3	STATION	2	PLAN 3	STATION	3			
RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	
.10	42.	1622.9	44.00	.10	42.	1621.2	44.00	
PLAN 4	STATION	2	PLAN 4	STATION	3			
RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	RATIO	MAXIMUM FLOW,CFS	MAXIMUM STAGE,FT	TIME HOURS	
.10	42.	1622.9	44.00	.10	42.	1621.2	44.00	

LAKE
BRACH
paa

F. J. NELSON
FOND
DAM

LAKE QUINN
BREACH ANALYSIS
PAGE 7/10

PLAN 1	STATION	4		PLAN 1	STATION	5	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	42.	1401.6	44.33	.10	42.	1352.1	44.67

PLAN 2	STATION	4		PLAN 2	STATION	5	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	42.	1401.6	44.33	.10	42.	1352.1	44.67

PLAN 3	STATION	4		PLAN 3	STATION	5	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	42.	1401.6	44.33	.10	42.	1352.1	44.67

PLAN 4	STATION	4		PLAN 4	STATION	5	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	42.	1401.6	44.33	.10	42.	1352.1	44.67

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
		1403.00	1403.00	1403.10	.10	1404.62	1.52	477.	358.	31.33	43.33	0.00
		380.	380.	385.								
		0.	0.	0.								

PLAN 2	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
		1403.00	1403.00	1403.10	.10	1404.62	1.52	477.	358.	31.33	43.33	0.00
		380.	380.	385.								
		0.	0.	0.								

F.F. 100.00
F.S. 100.00
DAM

PLAN 3	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
		1403.00	1403.00	1403.10	.10	1404.62	1.52	477.	358.	31.33	43.33	0.00
		380.	380.	385.								
		0.	0.	0.								

PLAN 4	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
		1403.00	1403.00	1403.10	.10	1404.62	1.52	477.	358.	31.33	43.33	0.00
		380.	380.	385.								
		0.	0.	0.								

LAKE QUINN
BREACH ANALYSIS
PAGE 3/10

PLAN 1 STATION 7				PLAN 3 STATION 8			
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	358.	1395.0	43.33	.10	358.	1370.4	43.33
PLAN 2 STATION 7				PLAN 4 STATION 8			
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	358.	1395.0	43.33	.10	358.	1370.4	43.33
PLAN 3 STATION 7				PLAN 1 STATION 9			
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	358.	1395.0	43.33	.10	358.	1358.8	43.33
PLAN 4 STATION 7				PLAN 2 STATION 9			
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	358.	1395.0	43.33	.10	358.	1358.8	43.33
PLAN 1 STATION 8				PLAN 3 STATION 9			
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	358.	1370.4	43.33	.10	358.	1358.8	43.33
PLAN 2 STATION 8				PLAN 4 STATION 9			
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	358.	1370.4	43.33	.10	358.	1358.8	43.33

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1		ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM			
		STORAGE	1353.00	1352.00	1353.00			
		OUTFLOW	305.	190.	305.			
			190.	0.	190.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS	
.10	1354.61	1.61	546.	1094.	9.00	44.67	0.00	
PLAN 2		ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM			
		STORAGE	1353.00	1352.00	1353.00			
		OUTFLOW	305.	190.	305.			
			190.	0.	190.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS	
.10	1354.53	1.53	532.	7794.	5.33	44.00	43.67	

LAKE QUINCY DAM

LAKE QUINCY
BREACH ANALYSIS

Page 9/10

PLAN 3

ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1353.00 305. 190.	SPILLWAY CREST 1352.00 190. 0.	TOP OF DAM 1353.00 305. 190.
---------------------------------	--	---	---------------------------------------

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX. OUTFLOW HOURS	TIME OF FAILURE HOURS
.10	1354.54	1.54	535.	6793.	5.67	44.67	43.67

LIVE
QUINN
DAM

PLAN 4

ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1353.00 305. 190.	SPILLWAY CREST 1352.00 190. 0.	TOP OF DAM 1353.00 305. 190.
---------------------------------	--	---	---------------------------------------

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX. OUTFLOW HOURS	TIME OF FAILURE HOURS
.10	1354.54	1.54	535.	6793.	6.54	45.67	43.67

PLAN 1	STATION	13	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	1095.	1342.3	44.67

PLAN 3	STATION	14	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	6173.	1330.4	45.00

PLAN 2	STATION	13	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	7690.	1346.7	44.00

PLAN 4	STATION	14	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	5277.	1329.6	45.00

STATION 14 =
DOWNSTREAM
DAMAGE CENTER
#1. DAMAGE
AT
ELEV. 932.

PLAN 3	STATION	13	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	6770.	1346.3	44.67

PLAN 1	STATION	15	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	1090.	1234.1	45.00

STATION 15 =
DOWNSTREAM ANAG
CENTER #2
DAMAGE AT
ELEV. 238.0

PLAN 4	STATION	13	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	5553.	1345.7	45.67

PLAN 2	STATION	15	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	5860.	1239.9	44.67

PLAN 1	STATION	14	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	1095.	1323.4	45.00

PLAN 3	STATION	15	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	5216.	1239.4	45.00

recall:
PLAN 2: Now failure
ALL OTHER PLANS
ARE BREACH
CONDITIONS

PLAN 2	STATION	14	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	7604.	1321.6	44.33

PLAN 4	STATION	15	
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	4604.	1238.9	46.00


FLOOD HYDROGRAPH PACKAGE - HET-1
DAM SAFETY VERSION JULY 1979
LAST MODIFICATION 01 APR 80

D-38

LIVE QUINN
BREACH ANALYSIS
Page 10/10

APPENDIX E

PLATES



WAYNE CO
1946
AMS 547 54 1546

Drainage Boundary


SOUTH

WAYNE CO
LACKAWANNA CO

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

LAKE QUINN DAM
DAVID BEYNON, SR
DRAINAGE AREA MAP

PLATE E - II





REPORT
ION PROGRAM

DAM
IN, SR

EA MAP

PLATE E-II





AD-A099 059

CORPS OF ENGINEERS BALTIMORE MD BALTIMORE DISTRICT
NATIONAL DAM INSPECTION PROGRAM. LAKE GUINN DAM (NDI ID NUMBER --ETC(U)
FEB 81

F/6 13/13

UNCLASSIFIED

NL

2 05 2

AD A
000000



END
DATE
FILMED
6-81
DTIC

APPENDIX F

GEOLOGY

LAKE QUINN DAM

GENERAL GEOLOGY

Bedrock at Lake Quinn is the Poplar Gap member of the Catskill Formation. It is medium-gray and light-olive-gray, fine- to coarse-grained sandstone and conglomerate with interbedded pale-red and grayish-red siltstone and shale. The rock is well bedded with sandstone and conglomerate thickly to very thickly bedded; shale and siltstone beds are medium to thick. The right abutment and base of the dam are of shale and sandstone of medium thickness. Joints and cleavage are well developed in thick-bedded rocks and are widely spaced; cleavage fractures are closely spaced. Fractures are open in surface exposures. Rock exposures are resistant to weathering. Fragments of sandstone and conglomerate are blocky and slabby, siltstone and shale fragments are platy, chippy and hackly.


Unconsolidated material overlying the bedrock surface may be thick. Water well drill records show 48 feet of glacial till in a domestic well near Lake Quinn. The unconsolidated material is sand and gravel with minor amounts of clay.

LEGEND

(Bedrock)

Dcd CATSKILL FORMATION, DUNCANNON MEMBER - Grayish-red sandstone, siltstone, and claystone in fining - upward cycles; conglomerate occurs at the base of some cycles.

Dcpp CATSKILL FORMATION, PACKERTON MBR. THROUGH POPLAR GAP MBR - Fine to medium-grained sandstones, well-indurated to quartzitic; sandstones grade upward into grayish-red siltstone and shales.



PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

LAKE QUINN DAM

DAVID BEYNON SR.

GEOLOGIC MAP

EXHIBIT F-1